

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 10 W.	C-11; C-12; C-13
2. PROPERTY CONTROLLING IN SECTION 31	T. 24 N. R. 10 W.	5; 10
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 29, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C. (continued)

5	10
Set 1"x36" pipe & post w/loc. tag	Found 1"x36" pipe & cedar post
3" W. Pine N37°W 57.6	6" Oak N36°E 78.2
8" Maple (tw) S84°E 31.4	9" Basswood N68°E 52.1
5" W. Pine S48°E 56.0	
3" R. Pine (tw) S17°W 40.1	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-11 Recovered and re-witnessed previous Department corner of record.
- C-12 Reestablished corner equidistant and on line between section corners, to north and south.
- C-13 Found 3/4" bolt in center of E-W gravel road, in line with old fence to north. Corner believed to be at same position as Devoe corner recovered by A.J. Teed in 1886.
- 5 Established corner equidistant and on line between N¼ corner & center of Sec. 31.
- 10 Recovered previous Department corner of record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11	C-12	C-13
Found DNR mon. & cedar post	Set Wexford Co. mon. & post w/loc. tag	Found 3/4" bolt, add 1"x24" pipe
5" R. Pine N86°W 52.2	6" R. Pine N80°W 53.1	Set post w/loc. tag Due N 33.0
8" Maple S46°E 21.1	6" R. Pine S54°W 62.6	14" Maple N46°E 81.0
7" Maple S15°E 38.2	12" B. Cherry S30°E 28.3	5" R. Pine N51°W 54.66
7" Maple S68°W 46.7	14" B. Cherry N49°E 50.1	Center blacktop road S
	Fence Corner, fence S & W N15°E 57	Due W 2

SIGNED BY Carl F. Roser 9-4-75 DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____



GREENWOOD TOWNSHIP
WEXFORD COUNTY