

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>24</u> N. <u>●</u> R. <u>10</u> W. <u>●</u>	A-11; A-12; A-13; D-13
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 29, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

*A. = Description of original monument and accessories and/or subsequent restoration*

C. (continued)

D-13  
 Found 1"x36" Pipe  
 Center E-W gravel road  
 Due N 2.5  
 5" S. Pine N32°W 56.25

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-11 Recovered and re-witnessed previous Department corner of record.
- A-12 Recovered previous Department corner of record.
- A-13 Found 3/4 iron rod in E-W gravel road. Corner in same position as corner recovered by Department in 1969.
- D-13 Found and accepted 1"x36" pipe in E-W road and in line with old fence to north and new fence to south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11	A-12	A-13
Found DNR mon. & post	Found DNR mon. & cedar post	Found 3/4" iron rod; loc. tag
8" Maple (cl) N74°W 18.6	9" Cedar S42°E 39.4	on <del>GR</del> fence post S05°E 37.2
10" Maple (tw) N27°W 59.9	5" Cedar S42°W 25.1	5" Maple N44°E 46.65
16" R. Pine S36°E 79.3	6" Maple S08°E 19.3	9" Maple N05°E 34.59
9" Maple (tw) N59°E 101.0		

SIGNED BY Carl F. Roser 9-4-75 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

GREENWOOD TOWNSHIP  
 WEXFORD COUNTY

