1,9, P.59

## **Land Corner Recordation Certificate**

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Craig W. McVean							Field Survey Date: Aug. 8, 2019							
For corner(s) in: Wexford			Count			_								
Original Public I	_and Survey	Corner			Corner Code									
S	Т		R											
s	T		R ¯		••••		A B (	וסכ	E F (	з н	J	K L I	M,	
s	Т		R ¯			_ 1							٦1	
S	Т		R _			2	6	- 5	4	3	2	11	2	
Property Controlling Corner					Corner Code	3	<del></del>	- 8-	l	10	- 11	12	3	
S	Т		R			-	-	,	5	10	1,1	12		
S	T		$R^{-}$			- 5	4'0	4-7	46		4 4	40	5	
S	T		R -			- 6	18	17	- 16 -	- 15	14	13	6	
S	T		$R_{\perp}^{-}$			7	!	•	-:.				7	
Property Corner					Corner Code	~ 8 9	19	20	21	22	23	24	8	
S 16	S T	24N	R	10W	15	_ 10	30	29	28	27	26	25	10	
S 17	T	24N	R ¯	10W	16	- ' <b>-</b> - 11							- 11	
\$	T		R ¯			- 12	- 31	- 32	33 -	- 34 -	- 35	- 36 -	1	
S	T		R _			- 1	- <b>-</b>	32	33	34	33	30	13	
Protracted Public Land Survey Corner					Corner Code	-13 <sup>l</sup>	\ В (	D	E F (	G H	الا	K L I	M	
S	T		R_											
s	Т		R _			***								
S	T		R			_								
S	T		R											

## Part A: Corner History

- 15 W 1/16 Corner common to Sec. 16 & 21, T24N, R10W
  - 1962 K. J. Ostling (PS # 10068) and LCRC L. 3, p. 38 (1977) - set 1" x 24" pipe
  - 1) 24" W. Pine stump S641/2°W 28.2' 2) 7" Cherry N241/2°E 53.3'

  - 1991 LCRC L. 4, p. 96, C.F. Roser (PS # 12028) Reset as established by Standard BLM instruction by K. Ostling in 1962 (Cor. destroyed by road – driveway work) Cor. falls at S. Edge of driveway west from Kolarvic Rd. (gravel in curve). Drove 5/8" x 34" rerod with LS cap.
  - 2) 12" Cherry N24°E 53.2';3) 12" Maple S64°W 67.4';

  - 4) P. Pole S82°E 51.36';
  - 5) Set Cedar post w/ Loc. Tag North 33'

- 16 E 1/16 Corner common to Section 17 & 20, T24N, R10W
  - None

## Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

15 – W 1/16 Corner common to Sec. 16 & 21, T24N, R10W
Found 5/8" Capped iron w/ cap # 12028 – 5.5±
South of centerline E-W sand drive. Condition of witnesses as follows; #1 – gone; #2 – Fair condition; #3 – Cut; #4 – OK; #5 – Fallen. 5/8" CIR accepted as the best available evidence of the position of the corner.

16 – E 1/16 Corner common to Sec. 17 & 20, T24N, R10W – Set 2" Aluminum cap on 5/8" x 34" rebar per Standard BLM procedure.

## Part C: Field Evidence of Perpetuation or Monumentation of Corner

15 – W 1/16 Corner common to Sec. 16 & 21, T24N, R10W 5/8" rebar w/ Plastic Cap #12028-down 0.7'. N 33.0' to set 2" Alum. Cap on 5/8" x 34" rebar on line w/ Blue Composite Post w/ Loc. Tag. N23°E 53.50' to set N & T in W. side 18" Cherry (#2) S80°E 51.35' to fd. PK nail in N. side P. Pole (#4) S63°W 36.45' to set N & T in SE side 8" Oak 16 – E 1/16 Corner common to Sec. 17 & 20, T24N, R10W
Stamped 2" Aluminum Cap on 5//8" x 34" long iron rebar. Set Blue Composite Post w/ Loc. Tag 1' SW. S39°W 68.39' to set N & T in SE side 15" Red Maple
N84°W 28.32' to set N & T in N. side 5" Cherry. S50°W 56.87' to set N & T in NE side 20" Cherry S26°21'W 220.10' to 2" Aluminum Cap stamped "WEXOP1".



Croy W. Me Van

Date

Craig W. McVeắn

Professional Surveyor's License No.:

39088

Prepared By: Craig W. McVean Michigan Dept. of Natural Resources 8015 Mackinaw Trail Cadillac, Michigan 49601