

**SURVEY &
REMONUMENTATION**

APR 25 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Wexford
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>24N</u>	R	<u>10W</u>	<u>1-13</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED

1994 NOV 23 PM 3:54

Linda Langhammer
WEXFORD COUNTY, MI
REGISTERED DEEDS

Register of Deeds Stamp & File Number

I, George D. Smith, in a field survey on July 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- I-13) 1838 GLO Section post by John Brink, Deputy Surveyor, Hemlock 12 N 46°E 38, Beech 11 N 55 1/2° W 25
- I-13) 1852 GLO Subdivision of Sections 2 & 3, T23N, R10W by L.S. Scranton, Deputy Surveyor, Beech 16 S 51° W 37, Beech 16 S 37°E 35
- I-13) 1886 A.J. Teed, Liber 1, page 282, Survey in Section 3, T23N, R10W, two witnesses ok, set stake and stone
- I-13) 1980 Wilcox LCRC, Liber 3, page 235, Found 4" Iron pipe, set Wexford Co. monument S 75°W 96.24' Power pole, N 33° W 94.35' 4" Red Pine, S 45° E 53.83' Tele riser, S 45° E 53.83' Tele riser, S 45°W 69.7' 15" Apple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A. con't

- I-13) 1980 Wilcox Certificate of Survey, Liber 1, page 847, set Wexford County monument
- I-13) 1987 Wilcox Certificate of Survey, Liber 2, page 370, found Wexford County monument
- I-13) 1993 Wilcox Certificate of Survey, Liber 72, pages 396-397, found Wexford County monument

B.

Found Wexford County monument with aluminum cap in good condition in centerline roads North-South and East-West. This corner is accepted as a careful and faithful perpetuation of the position of the original corner, being the Section corner common to Sections 34 and 35, T24N, R10W and Section 3 and 2, T23N, R10W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Wexford County monument with aluminum cap

- S 75° W - 96.21' - Power pole
- N 33° W - 94.25' - 4" Red Pine
- S 47° W - 70.50' - 15" Apple
- S 41° E - 84.82' - 4" Scotch Pine



Peer Group Reviewed and Approved
Date: 11-21-94
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by George D. Smith
Surveyor's Michigan License No. 39098

Date 11/17/94