

**SURVEY &
REMONUMENTATION**

APR 25 1995

RECEIVED

**COMMISSION
LAND CORNER RECORDATION CERTIFICATE**

1994 NOV 23 PM 3:54

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wexford
(County)

Located In:

Corner Code #

Linda Longbriller
WEXFORD COUNTY, MI
REGISTERED DEEDS

- | | | |
|---------------------------------------|-----------------------------|-------------|
| 1. Public Land Survey | T <u>24</u> N R <u>10</u> W | <u>K-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, George D. Smith, in a field survey on August 9, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- K-13) 1838 GLO Section post by John Brink, Deputy Surveyor, Sugar 14 N 14° E 22, Hemlock 13 S 21° E 26
 - K-13) 1852 GLO subdivision of Section 1 & 2, T23N, R10W by L.S. Scranton, Deputy Surveyor, found post, Beech 10 S 28° E 24, Beech 10 S 35° W 58
 - K-13) 1977 Wilcox survey for description, found 1/2" x 3" x 2 steel bar, set Wexford County monument in centerline East-West road and 6' West of centerline North-South road N 20° W 14" Elm stump 59.07', N 45° E fence corner 56.77', S 75° E 8" Scotch Pine 106.78'
 - K-13) 1980 Wilcox Certificate of Survey, Liber 1, page 847, found Wexford County monument
 - K-13) 1980 Wilcox Certificate of Survey, Liber 1, page 829, found Wexford County monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A. con't

- K-13) 1981 Wilcox Certificate of Survey, Liber 1, page 912, found Wexford County monument
- K-13) 1987 Wilcox Certificate of Survey, Liber 2, page 370, found Wexford County monument
- K-13) 1993 Wilcox Certificate of Survey, Liber 72, page 253, survey in Section 1, T23N, R10W, found Wexford County monument

B.

Found Wexford County monument in centerline roads East-West and 6' West of centerline roads North-South (in good condition). This corner is accepted as a careful and faithful perpetuation of the position of the original corner, being the Section corner common to Sections 35 and 36, T24N, R10W and Sections 2 and 1, T23N, R10W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Wexford County monument with aluminum cap

- S 69° E - 112.89' - Power pole
- S 23° E - 87.80' - Power pole
- S 45° W - 47.75' - 4" Cedar
- N 30° W 71.10' - 5" Spruce



Peer Group Reviewed and Approved

Date: 11-21-94
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by George D. Smith

Date 11/17/94

Surveyor's Michigan License No. 39098

LIBER 04 PAGE 284