

**SURVEY &  
REMONUMENTATION**

APR 25 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED

1994 DEC -9 PM 4: 24

*Linda Loughmiller*  
WEXFORD COUNTY, MI  
REGISTERED CLERK

For corners in

<u>Wexford</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>10W</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, George D. Smith, in a field survey on August 9, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- L-13) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor, 12" dia Maple Quarter Section corner
  - L-13) 1977 Wilcox survey for description, found angle iron set Wexford County monument in centerline road and in fence line North-South, North 21.16' fence corner, N 55° E 126.39' power pole, S 30° W 75.43' 6" Elm
  - L-13) 1980 Wilcox Certificate of Survey, Liber 1, page 829, found Wexford County monument
  - L-13) 1981 Wilcox Certificate of Survey, Liber 1, page 312, found Wexford County monument
  - L-13) 1993 Wilcox Certificate of Survey, Liber 72, page 253, survey in Section 1, T23N, R10W, found Wexford County monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found Wexford County monument (good condition) ± 1' North centerline roads East-West and in fence lines North-South. This corner is accepted as a careful and faithful perpetuation of the position of the original corner, being the 1/4 corner common to Section 36, T24N, R10W and Section 1, T23N, R10W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Wexford County monument with aluminum cap

- S 30° W - 75.16' - 10" Elm
- S 4° W - 33.00' - 1/2" Iron & cap #14102
- N 71° E - E 126.58' - Power pole
- N 5° E - 21.55' - Fence corner
- S 9° W - 52.40' - 5" Elm

Peer Group Reviewed and Approved  
Date: 12-9-94  
*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor



LIBER **004** PAGE **322**  
Signed by *George D. Smith*  
Surveyor's Michigan License No. 39098

Date 11/17/94