

RECEIVED

APR 16 1998

RECEIVED

1998 DEC 30 PM 2: 10

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

<u>Wexford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>10W</u>	<u>M-2</u>
2. Property Controlling in Section	S _____ T _____	<i>Common to: A-2 T24N, R9W</i>
3. Miscellaneous Property in Sec.	S _____ T _____	
	S _____ T _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, George D. Smith, P.S., in a field survey on April 16, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-2) 1838 GLO Quarter Section Post by John Brink, Deputy Surveyor; Maple 7-N28W-22; Hemlock 9-S67W-36
- M-2) 1913 Fargo Engineering Co. Found stake and roots of 2 U.S. witnesses. Cedar stump N08W, 0.36', Cedar stump S72E, 11 1/2'.
- M-2) 1980 Roser, PS #12028 LCRC Liber 3, Page 231, found fargo butter dish and stake bottom shadow. Replaced fargo corner with Wexford County Monument. 10" cedar N66°W 20.3', 8" maple S23°W 15.7', 7" Maple N33°E 14.3', centerline north-south trail road east ± 97'
- M-2) 1985 Consumer Power Survey, Liber 2, Page 75 (copy not legible).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-2) Found Wexford County Monument and one witness from 1980 Roser PS #12028 LCRC. This corner is accepted as a careful and faithful perpetuation of the position of the original corner, being the quarter corner common to Section 1, T24N, R10W and Section 6, T24N, R9W

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-2
Wexford Co. Monument with aluminum cap stamped E 1/4 1, 1998, PS 39098.
N65W 20.72' 12" Cedar (20.3' Roser)
S45W 14.29' 12" Hemlock
N35E 14.66' 8" Maple
East 6.75' 10" Cedar

Peer Group Reviewed and Approved
Date: 4 December 1998
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by *George D. Smith*
Surveyor's Michigan License No. 39098

Date 12-9-98



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995