

APR 16 1998

SECTION

RECEIVED

1998 DEC 30 PM 2:10

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Linda Longmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

Wexford Located In: Corner Code #
(County)

1. Public Land Survey T 24N R 10W M-3
T _____
T _____
T _____ *Common to:*

2. Property Controlling S _____ T _____
in Section S _____ T _____ *A-3*

3. Miscellaneous S _____ T _____
Property in Sec. S _____ T _____ *T24N, R9W*

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, George D. Smith, P.S., in a field survey on April 4, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-3) 1838 GLO Section Post by John Brink, Deputy Surveyor; Beech 10 N46 1/2 W 26, Beech 16 S21 1/2 W 34.
- M-3) 1852 GLO Subdivision of T24N, R9W by VW Caukin, Deputy Surveyor; Hemlock 18 S2E 9, Hemlock 10 N70E 12.
- M-3) 1913 Fargo Survey found no us evidence reestablished corner a proportional measure between found E 1/4 section 1 and found SE corner section 12, W.P. stump S16 1/2 W 1.22, W. Pine stump 20 N10E 3.03 3/4.
- M-3) 1980 C. Roser, PS #12028 LCRC Liber 3, Page 230, Reestablished SE corner Sec. 1 equidistant and on line between found Fargo 1/4 corners 1/2 mile to North and South. While setting corner, found stake shadow, line remains and pine stump witness remains S16 1/2 W. Set Wexford Co. Mon., 6" Red pine N35E 7.2, 8" Red pine N80W 3.4, 6" Tw red pine S30E 8.7.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-3) Found Wexford County Monument and one witness from 1980 Roser LCRC, ± 78' easterly of North-South trail and 45' ± southerly of easterly trail. This corner is accepted as a careful and faithful reestablishment of the position of the original corner, being the section corner common to Sections 1 and 12, T24N, R10W and Sections 6 and 7, T24N, R9W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-3
Wexford Co. Monument with aluminum cap stamped SE 1, 1998, PS 39098
N35E 10.52' 8" Red pine, found spike
East 4.20' 10" Red pine, found spike
S35W 14.40' 10" Red pine, found spike
N85W 3.82' 10" Red pine, found spike

Peer Group Reviewed and Approved

Date: 4 December 1998
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by George D. Smith
Surveyor's Michigan License No. 39098

Date 12-9-98

