

**SURVEY &
REMONUMENTATION**

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1994 DEC -9 PM 4: 24

For corners in

Wexford
(County)

Located In:

Corner Code #

Ronda Loughmiller
WEXFORD COUNTY, MI
REGISTERED DEEDS

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>24N</u> R <u>10W</u> | <u>M-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, George D. Smith, in a field survey on June 14, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-7) 1838 GLO Section post by John Brink, Deputy Surveyor, Tamarack 10, N 65 1/2° W 17, Tamarack 9, S 24 1/2° W 21
- M-7) 1852 GLO subdivision of Section 18 & 19, T24N, R9W by V.W. Caukin: Found post, 12 Tamarack N 75° E 34, 12 White Pine S 78° E 30
- M-7) 1895 A.J. Teed Survey, Liber 1, page 320 in Section 19, T24N, R9W: Found stake, no witnesses given
- M-7) 1981 Wilcox LCRC, Liber 3, page 257: Set Wexford County monument by single proportionate measure between found NE corner of Sec. 13 and found NE corner of Sec. 25, in centerline North-South road and South edge of trail West, 6" Maple N 85° E 49.82', 8" White Birch S 41° E 46.91', Northwest corner bridge rail S 14° W 87.18', 10" Spruce S 88° W 37.55'
- M-7) 1985 Wilcox Certificate of Survey, Liber 2, page 147: Found Wexford County monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Wexford County monument 1' Westerly of centerline North-South road. This corner is accepted as a careful and faithful reestablishment of the position of the original corner, being the Section corner common to Sections 13 and 24, T24N, R10W and Sections 18 and 19, T24N, R9W.

Peer Group Reviewed and Approved
Date: 12-9-94
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" Iron with Wexford County brass cap, stamped SE 13, 1994, PS 33989

- S 40° E - 46.85' - 8" White Birch stump
- S 14° W - 87.11' - Northwest bridge rail at bottom of rail
- S 35° E - 58.84' - 18" White Pine
- N 86° E - 27.16' - Telephone riser post
- S 68° E - 74.11' - 7" Twin Maple

LIBER **004** PAGE **313**

Signed by *George D. Smith*
Surveyor's Michigan License No. 39098

Date 11/29/94

