

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1994 NOV 23 PM 3:53

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

Wexford
(County)

Located In:

Corner Code ##

- | | | | | | |
|------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>24N</u> | R | <u>10W</u> | <u>M-9</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, George D. Smith, in a field survey on June 14, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-9) 1838 GLO Section post by John Brink, Deputy Surveyor, 16 Hemlock N 36 1/2° W 42, 16 Hemlock S 36° W 36
- M-9) 1852 GLO Section subdivision of Section 19, T24N, R9W by V.W. Caukin, Deputy Surveyor: Found post, 18" Hemlock S 31° W 56, 8" Hemlock N 43° E 21
- M-9) 1895 A.J. Teed survey in Section 19, T24N, R9W: Found stake, 30" Pine S 34° W 32 links
- M-9) 1980 Roser LCRC, Liber 03, page 260: Found 3/4" bolt from Wexford County Road Commission witnesses, set Wexford County monument 15" Twin Maple N 65° E 112.68', 16" Cherry N 60° W 87.63', 15" Cherry S 10° E 102.12, power pole S 50° E 48.18', Cedar post with loc. tag S 45° E 47'
- M-9) 1990 Wood LCRC, Liber 04, page 56: Found 3/8" steel rod, tele box N 45° E 69.3', power pole S 50° E 48.75', 12" Cherry S 60° W 87.67'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Wexford County monument in good condition, 2' South of centerline of East-West roads and 2.5' East of centerline roads North-South. This corner is accepted as a careful and faithful perpetuation of the position of the original corner, being the Section corner common to Sections 24 and 25, T24N, R10W and Sections 19 and 30, T24N, R9W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Wexford County monument with aluminum cap

- S 44° E - 48.76' - Power pole
- N 64° E - 112.65 - 16" Maple
- N 61° W - 87.63' - 18" Cherry
- S 35° E - 47.07' - Face of Cedar post
- S 07° E - 102.07' - 18" Cherry
- S 57° W - 48.60' - 7" Poplar



Peer Group Reviewed and Approved

Date: 11-21-94
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by George D. Smith
Surveyor's Michigan License No. 39098

Date 11/17/94