

**SURVEY &
REMONUMENTATION**

APR 25 1995

RECEIVED

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

1994 NOV 23 PM 3: 53

For corners in

Wexford
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>24N</u> R <u>10W</u> | <u>M-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, George D. Smith, in a field survey on June 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- M-10) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor, 12 Elm N 67° E 82
 - M-10) 1895 A.J. Teed Survey in Section 30, T24N, R9W: Set corner, no description given, on line between NW and SW corners at 1/2 the distance, 4" Black Ash N 68° E 21
 - M-10) 1979 Wood Certificate of Survey, set 1/2" iron w/ cap, 16" Maple S 40° E 49.37', 10" Chinese Elm N 70° E 29.35'
 - M-10) 1980 Roser LCRC, Liber 3, page 260: Found and accepted 1/2" re-rod set by R.L.S. G. Gray and D. Wood for the West 1/4 of Section 30, T24N, R9W, replaced with Wexford County monument, 13" Elm stump N 30° W 27.09', 12" Maple S 35° E 49.42', 5" Ash N 75° E 29.27', Cedar post with loc. tag East 33'
 - M-10) 1990 D. Wood LCRC, Liber 04, page 56: 1/2" steel re-rod, power pole AZ 140° 49.37', 10" Chinese Elm AZ 70° 29.35', 11" steel pipe AZ 350° 147.85'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found standard Wexford County monument in good condition opposite drainage ditch to West and 1.5' ± West of centerline of North-South road. This corner is accepted as a careful and faithful reestablishment of the position of the original corner, being the 1/4 corner common to Section 25, T24N, R10W and Section 30, T24N, R9W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Wexford County monument with aluminum cap

- N 30° W - 27.10' - 13" Elm stump
- N 76° E - 29.22' - 8" Ash stump
- N 5° W - 148.13' - Pk-nail in concrete headwall ±3.5' East of West end of headwall
- S 82° W - 53.55' - 1/2" x 18" Iron
- S 40° E - 52.95' - 1/2" x 18" Iron
- S 68° E - 52.35' - 1/2" x 18" Iron
- N 24° E - 49.92' - Pk-nail in East side of 12" CMP

Peer Group Reviewed and Approved

Date: 11-21-94
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by George D. Smith
Surveyor's Michigan License No. 39098

