

**SURVEY &  
REMONUMENTATION**

APR 25 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED

1994 DEC -9 PM 4: 24

For corners in

Wexford

(County)

Located In:

Corner Code #

- |                                       |                           |             |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey                 | T <u>24N</u> R <u>10W</u> | <u>M-12</u> |
|                                       | T _____ R _____           | _____       |
|                                       | T _____ R _____           | _____       |
|                                       | T _____ R _____           | _____       |
| 2. Property Controlling in Section    | S _____ T _____ R _____   | _____       |
|                                       | S _____ T _____ R _____   | _____       |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____   | _____       |
|                                       | S _____ T _____ R _____   | _____       |
| 4. Lot No. _____, Recorded Plat _____ |                           |             |
| 5. Private Claims _____               |                           |             |

*Linda Loughmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, George D. Smith, in a field survey on June 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- M-12) 1838 GLO Quarter Section post by John Brink, Deputy Surveyor, 9 Beech S 16 1/2° W 32, 14 Beech S 47° W 58
- M-12) 1907 D.E. Teed survey, Liber 1, page 348: Set stake on line between found Northeast corner and Southeast corner at 1/2 distance, tele pole N 81° W 31', tele brace S 33 1/2° E 76'
- M-12) Wexford County Road Commission witnesses 18" Poplar S 60° E 36.80', old witness book Cedar post N 90° E 25.25', Cedar post N 45° E 50.20'
- M-12) 1975 J.L. Wilcox LCRC, Liber 2, page 744: Found 1 1/2" pipe in centerline road 3' South of fence line, 24" Cottonwood S 35° E 41.10', tele pole N 85° E 24.92', fence post N 35° E 43.17'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A. con't

- M-12) 1978 J.L. Wilcox Certificate of Survey, Liber 1, page 674: Corner found
- M-12) 1979 Wood Certificate of Survey (unrecorded), Found Iron 24" Cottonwood S 35° E 41.10', telephone pole N 85° E 24.92', fence post N 35° E 43.17'
- M-12) 1987 J.L. Wilcox Certificate of Survey, Liber 2, page 352: Corner found

Peer Group Reviewed and Approved

Date: 12-9-94

*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

Found 1/2" Iron and cap #14102 in center of 1 1/2" pipe ±4.5' East of Centerline of road North-South and in centerline of road to West. This corner is accepted as a careful and faithful reestablishment of the position of the original corner, being the 1/4 corner common to Section 36, T24N, R10W and Section 31, T24N, R9W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron with Wexford County brass cap, stamped E 1/4 36, 1994 PS 33989 in center of 1 1/2" pipe

- S 40° E - 41.10' - 24" Cottonwood
- S 85° E - 32.52' - Corner fence post
- S 22° E - 40.37' - Pk-nail in North side of 12" CMP
- N 53° E - 55.85' - 4" Apple (in clump)
- S 62° E - 30 - Set 32 18" iron at Southeast corner of phone riser

LIBER 004 PAGE 315

Signed by George D. Smith  
Surveyor's Michigan License No. 39098

