

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY


T 24 N R 10 & 11 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 6 & 1

CORNER MONUMENT Set Std. Dept. Mon & Cedar Guard Post

DATE MONUMENT PLACED AND WITNESSED 7-8-70

WITNESSES TO CORNER.....



5" W. Pine S 23 W 18.7'

6" W. Pine N 75 E 8.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered while making a retracement survey in this area. We were able to reconstruct the corner from the stump remains (J. Pine) of three old witnesses by E. P. Waterman. One stump still showed lower face and notch. See survey by E. P. Waterman, Sept. 1909. Notes in possession of Walt Fraser, RLS, Traverse City.

SURVEYOR'S SEAL

SIGNED

Carl F. Roer

DATE 7-17-70

DISTRIBUTION:

REGISTERED LAND SURVEYOR 12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68