

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
WEXFORD

(County)

Located In:

Corner Code //

- | | | |
|------------------------------------|---------------------------|----------|
| 1. Public Land Survey | T <u>24N</u> R <u>11W</u> | 1-7, 1-8 |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, C.F. ROSE, in a field survey on OCTOBER, 31, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration.

I-7
 (NO EVIDENCE OF G.L.D. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.D. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

I-7 CONT.
 I-7 PART B. CONT.
 U.S.B.T. "SITE" SE (HEMLOCK) &
 U.S.B.T. "HOLE" NW (W.PINE).
 HIS NOTES ALSO SAY "C.P.C. COR IS 1.06(CH) S & 0.83(CH) E".

I-7 CONT.
 SCHAAF'S ACTUAL NOTE'S - HE HAVING DONE CONSIDERABLE WORK IN OTHER TWP'S FOR WHICH THERE ARE NO NOTE'S AVAILABLE). ABOVE FARGO PIPE AS FD ON 10-05-87 (& SET SO'D CED POST ON 10-05-87) WERE REMOVED BY DEER HUNTER'S AND - OR TIMBER CUTTING OPERATION. ON 10-31-94

I-8 B CONT.
 ON SIDE OF "DESCEND BANK TO RV. FLOOD PLANE". FARGO (1913) SAYS NO US EVIDENCE. M.SCHAAF (1940) SAYS "FD SE USBT STILL STANDING, LOWER FACE CHOPPED OUT & UPPER OVER GROWN". C.P. COR BEAR'S S48 1/2°E, 71 LKS. NO SCHAAF MON FD. ACCEPT FD FARGO (C.P.C.) COR!

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I-7
 ON 10-05-87, RLS C.F.ROSER & WILDLIFE TECH. R.WESTBROOK, FOUND FARGO ENGR.(1913-C.P.C.) 1" PIPE THAT FIT BOTH FARGO STUMP REMAINS FOR N.B.T.'S. FARGO NOTES INDICATE THEY HAD U.S. B.T. REMAINS AND REMAINS OF OLD STAKE. MARCUS SCHAAF; STATE FORESTER & RLS(DECEASED) WAS HERE ON 10/22/40 AND HIS NOTES INDICATE HE HAD U.S. COR LOCATED BY -CONT. ABOVE RIGHT

I-7 CONT.
 SCHAAF ALSO TOOK THREE N.B.T.'S (W.PINE STP'S), THE REMAINS OF WHICH ARE STILL EVIDENT. APPARENTLY A SCHAAF PIPE MON. WAS NEVER SET (OR WAS REMOVED) AS THERE IS NO EVIDENCE OF SAME NOW. HIS(SCHAAF) N.B.T.'S DO FIT HIS ABOVE TIE TO C.P.C. (FARGO) COR. THIS SURVEYOR DEFINITELY ACCEPTS THE FARGO COR, AS THEIR NOTE'S ARE VERY CLEAR THAT THEY HAD US(GLO)

I-7 CONT.
 PROBED FOR HOLE OF REMOVED SQUARED CEDAR POST; FOUND AND DUG AND FOUND FARGO(1913) BUTTER DISH. SET D.N.R. MON AND CEDAR POST AND TOOK ABOVE NOTED N.B.T.'S. (I-7, item "C")

I-8
 FD FARGO ENGR. (1913 SUR WORK FOR CO.PO.CO.) 3/4"(I.D.)x 30" GALV. IR. PIPE W/L END, LYING ON GROUND BESIDE ROTTED OFF, SCRIBED, OLD, LARGE, SO'D CED POST. DUG DOWN 6" & FD FARGO BUTTER DISH. DROVE 1"x 48" GALV. PIPE W/ALUMN. DNR CAP, BESIDE FD BUTTER DISH; FITS BOTH FARGO 1913 NBT'S. LEFT FARGO PIPE BURIED BESIDE DNR MON. COR FALLS -- CONT. ABOVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

I-7
 FD. FARGO ENG. BUTTER DISH AND SET DNR MON. & CED. POST.
 12"W.PINE N75°W 61.44'
 18" MAPLE N35°E 60.30'
 18" R.PINE S40°E 63.30'
 12" R.PINE S30°W 45.76'
 TOP OF BANK (DESCENDS SOUTH TO BOTTOM LAND) SOUTH 125'±15'

I-7 CONT.
 GOVT. COR IN MARCH-APRIL 1913. THERE IS NO EVIDENCE THAT SCHAAF'S POSITION WAS EVER "HONORED" OR USED; IN FACT NO ONE WOULD KNOW OF HIS CORNER POSITION UNLESS THEY HAD CONTACTED THE CONSERVATION DEPT IN ROSCOMMON (THIS IS ONE OF THE FEW TWP'S WHERE WE HAVE -- CONT. ABOVE RIGHT --



I-8
 FD FARGO COR, REPLACED W/DNR MON. SET CEDAR POST.
 6"W.PINE (GROWING IN FARGO 1913 W.PINE WIT STP) N35°E 19.17'
 11" CEDAR S05°W 16.75'
 3" CEDAR S80°W 7.70'
 22"HEM(FARGO WIT) N37 1/2°W 17.20'
 BOTTOM OF BANK WEST 20'±
 TOP OF BANK EAST 45'±
 E'LY EDGE MANISTEE RV. W 140'±

Signed by Carl F. Roser 12028

Date 12-12-94

Surveyor's Michigan License No. _____