

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 11	H-3, H-4, H-5
2. PROPERTY CONTROLLING IN SECTION	10, T. 24 N. R. 11	8, 13
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JAN 8, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

C. (CONTINUED)

<p style="text-align: center;">8</p> <p>SET 5/8" X 34" REROD W/RLS CAP & SET CED POST W/LOC TAG. 8" CED S15°W 3.5 14" HEMLOCK N40°W 12.6 8" CED N05°W 17.5</p>	<p style="text-align: center;">13</p> <p>FD 1/2" X 18" REROD, REPLACED W/ 5/8" X 34" REROD W/RLS CAP & SET CED POST W/LOC TAG. 11" IRONWD S72°E 49.55 10" R PINE N14°E 22.05 11" R PINE N42°W 24.88</p>
--	---

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-3 RE-ESTAB 1/4 COR MID-WAY & ON LINE BETW FD NE & NW COR'S OF SEC 10. COR FITS W.PINE STUMP REMAINS OF 1915 N.B.T. (MICH CIVIL ENGR & CONST CO), N72°W, 88.0'. COR FALLS 0.5'±N OF CTR OF E-W B-TOP RD. A N-S FN (NORTH) IS 127' EAST.
- H-4 ESTAB CTR OF SEC 10 AT INTERSEC. OF ONE-QUARTER LINES. A G.F. & A. 5/8" X 16" REROD UNDER LOG (NAIL DRIVEN IN LOG ABOVE IR.) IS N41°46'E 6.77' (LEFT IN PLACE). THE CTR OF ANDERSON CRK (IN CURVE) IS 15'±N & 17'±E.
- H-5 FD 1 1/2" PIPE (WELL POINT) IN CTR OF E-W GRAVEL RD & IN LINE W/OLD LINE FN'S TO N & S.
- 13 FD 1/2" X 18" REROD FOR NW COR OF SE 1/4 - SE 1/4 OF SEC. 10.
- 8 ESTAB SE COR OF W 1/2 OF NW 1/4 OF SEC 10 MID-WAY & ON LINE BETW W 1/4 COR & CTR OF SEC 10. E-W WINDING FN IN TREES IS NORTH 27'±

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3	H-4	H-5
DRIVE 3/4" X 18" SOLID IR ROD.	DRIVE 1" X 62" PIPE W/RLS CAP	FD 1 1/2" PIPE (WELL PT)
16" W PINE N70°W 100.94	& SET CED POST W/LOC TAG.	24" CHERRY S05°W 29.25
8" W PINE N34°W 65.02	8" CED N26°E 15.92	14" MAPLE S12°E 39.55
8" MAPL CLUMP S12°W 51.25	6" CED N82°E 13.73	8" CED S34°W 41.95
6" MAPLE S60°E 64.80	7" TW CED N34°W 6.16	FD RLS CAP
SET CED POST	18" CED N66°W 44.48	#14102 NORTH 33.00
W/LOC TAG. NORTH 33'		

SIGNED BY Carl F. Roser 01-14-85 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



(SEAL)

HANOVER TWP.
WEXFORD COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____