

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 11 W.	G-3, G-4, G-5
2. PROPERTY CONTROLLING IN SECTION	10, T. 24 N. R. 11 W.	1
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JAN 8, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

C. (CONTINUED)

G-5	1
FD 1/2" ROD W/RLS CAP #13030.	DROVE 5/8" X 17" REROD W/RLS CAP.
16" MAPLE N46°E 66.90	14" W PINE N78°E 156.48
10" R PINE S30°E 58.77	12" CEDAR S42°E 50.50
12" MAP CLUS S56°E 80.80	13" TAMARACK S38°W 108.88
6" OAK S36°W 60.66	SET CED POST
SET CED POST	W/LOC TAG. SOUTH 33'
W/LOC TAG. S45°W 47'±	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-3 FD IR W/RLS CAP #13030; GLEN DELAMATER. COR IS IN CTR OF E-W B.TOP RD & IN LINE WITH APPROX CTR OF GRAVEL RD TO SOUTH. A FN TO NORTH IS WEST 5 TO 6 FEET.

G-4 FD 3/8" PIPE W/BROKEN RLS CAP, OCT 1983. IN NOV 1984 FD STD WEXFORD CO MONUMENT. FN EAST (TO EAST) IS APPROX 1 FOOT SOUTH. AT 350'± EAST, FENCE SWINGS OFF E-NE (VERY IRREGULAR). COR FALLS IN APPROX CTR OF N-S GRAVEL ROAD.

G-5 FD ROD WITH GLEN DELAMATER RLS CAP. COR IS IN LINE W/CTR OF GRAVEL ROAD TO N AND IS 3'± N OF CTR OF GRAVEL RD TO E & CTR OF TRAIL RD W. CTR OF TRAIL TO S IS 4'±E. SOURS HAD A SURVEY THROUGH THIS AREA IN 1916.

I ESTAB NE COR OF W1/2-NW1/4 OF SEC 10 MID WAY & ON LINE BETW N1/4 COR & NW COR OF SEC 10. COR FALLS IN APPROX CTR OF E-W B-TOP RD. CTR OF 18" CONC CULV IS WEST 15.5'±.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3	G-4
FD IR W/RLS CAP #13030.	FD WEXFORD CO MON.
FENCE POST N06°W 38.40	10" TW CHERRY S32°W 96.41
6" R PINE S48°W 72.42	16" CHERRY N82°E 111.75
8" W PINE S48°E 127.80	10" TRIP CHERRY S60°E 39.41
CTR US SURVEY	10" W PINE N36°E 93.29
ELEV MRKR 1019' N18°W 37.80	
SET CED POST	
W/LOC TAG. NORTH 33'	

SIGNED BY Carl F. Roser 01-14-85 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)  
HANOVER TWP  
WEXFORD COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_