

APR 25 1995

RECEIVED

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC -9 PM 2:58

For corners in

| | | |
|------------------------------------|---------------------------|----------------|
| <u>WEXFORD</u> County | Located In: | Corner Code ## |
| 1. Public Land Survey | T <u>24N</u> R <u>11W</u> | <u>B-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Linda Longmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

CRAIG J. PULLEN JUNE 22 19 94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B-13 1838 GLO SURVEY BY J. BRINK WOOD POST HEM 11 N38E 27 HEM 10 N53½W 16
1903 D.E. TEED SURVEY IN SEC.6, T23N, R11W FOUND IRON PIPE SHOWN TO ME BY DEVOE AND HARVEY BURT. W. PINE 40 N55½W 138½L W. PINE ROOT S6 3/4W 51½L
1913 FARGO ENGINEERING SURVEY IN SEC.31, T24N, R11W FOUND IRON DRAG TOOTH ACCEPTED. NW CORNER OF CEMENT BLOCK HOUSE OF ELMER KLEEMAN S38½E 1.44 CH TEL. POLE N14¼W 0.38 3/4 CH
1978 WILCOX & ASSOC. SURVEY J.L. WILCOX PS#14102 L.1 P.617 FOUND FARGO CORNER 3/4" IRON. SET WEXFORD COUNTY MONUMENT. NORTH FENCE POST 35.11' N45°E 10" ELM 61.68' N30°W 8" JACK PINE 45.97' S38°E 10" APPLE TREE 90.54'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-13 FOUND WEXFORD COUNTY MONUMENT IN CENTERLINE OF ROAD AND ONE 1978 WITNESS. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER, BEING THE ¼ CORNER COMMON TO SECTION 31, T24N, R11W AND SECTION 6, T23N, R11W.

Peer Group Reviewed and Approved

Date: 12-2-94

Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-13 S¼ CORNER, SECTION 31, T24N, R11W
WEXFORD COUNTY MONUMENT
N47°W 8" RED PINE 62.00'
S36°E END OF FENCE POST
IN RIGHT-OF-WAY 40.49'
N4°E CORNER FENCE POST 35.55'
N40°E 16" TWIN MAPLE 96.23'



LIBER 04 PAGE 302

Signed by *Craig J. Pullen*
Surveyor's Michigan License No. 39095

Date NOVEMBER 22, 1994