

**SURVEY & RECORD DOCUMENTATION**

RECEIVED

APR 25 1995

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

1994 DEC -9 PM 2: 58

**COMMISSION**

For corners in  
**WEXFORD**

(County)

Located In:

Corner Code #

- |                                    |   |     |   |     |      |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey              | T | 24N | R | 11W | D-13 |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
| 2. Property Controlling in Section | S |     | T | R   |      |
|                                    | S |     | T | R   |      |
| 3. Miscellaneous Property in Sec.  | S |     | T | R   |      |
|                                    | S |     | T | R   |      |

*Linda Loughmiller*  
 WEXFORD COUNTY, MI  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

CRAIG J. PULLEN

JUNE 22

94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- D-13 1838 GLO SURVEY BY J. BRINK, WOOD POST HEM 9 N30E 12 SUGAR 9 N33W 26  
 1913 FARGO ENG. SURVEY IN T24N R11W FOUND IRON PIPE AND BURIED CROCKERY. ACCEPTED. TELEPHONE POLE N69°W 0.99½ CH TELEPHONE POLE N78½E 1.56½ CH  
 1977 J.L. WILCOX PS#14102 L.C.R.C. P.3 L.171 SET WEXFORD COUNTY MONUMENT BY S.P. ON BASIS OF SURVEY OF RECORD (FARGO) N55°E 40" CLUMP ELM 49.31' N40°W 2" CEDAR 52.24' S30°E 3" CHERRY 34.23' S75°W 4" POPLAR 125.73'  
 1980 J.L. WILCOX & ASSOC. SURVEY L.1 P.853 WEXFORD COUNTY MON. WITNESSES SAME AS 1977.  
 1987 J.L. WILCOX & ASSOC. SURVEY L.66 P.523 WEXFORD COUNTY MONUMENT WITNESSES SAME AS 1977.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-13 FOUND WEXFORD COUNTY MONUMENT IN GOOD CONDITION AND 2 PREVIOUS WITNESSES. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER, BEING THE ¼ CORNER COMMON TO SECTION 32, T24N, R11W AND SECTION 5, T23N, R11W.

Peer Group Reviewed and Approved  
 Date: 12-2-94  
*Richard D. Wilcox*  
 Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-13 S¼ CORNER, SECTION 32, T24N, R11W  
 WEXFORD COUNTY MONUMENT  
 N54°E 42" ELM STUMP (NEW NAIL) 50.35'  
 NORTH ½" IRON #14102 33.00'  
 N50°W 6" CEDAR CLUMP 52.09'  
 S44°W ½" PIPE WITH COUPLING 31.31'



LIBER 04 PAGE 304

Signed by *Craig J. Pullen*

Date NOVEMBER 22, 1994

Surveyor's Michigan License No. 39095