

**SURVEY & REINUMENTATION**

APR 25 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED

1994 DEC -9 PM 2:58

For corners in  
**WEXFORD**

*Linda Loughmiller*  
 WEXFORD COUNTY, MI  
 REGISTER OF DEEDS

	(County)	Located In:		Corner Code #
		24N	11W	
1. Public Land Survey		T _____ R _____	E-13	_____
		T _____ R _____		_____
		T _____ R _____		_____
		T _____ R _____		_____
2. Property Controlling in Section		S _____ T _____ R _____		_____
		S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.		S _____ T _____ R _____		_____
		S _____ T _____ R _____		_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

CRAIG J. PULLEN

AUGUST 17

94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- E-13 1838 GLO SURVEY BY J. BRINK, WOOD POST SUGAR 10 N52½E 25 SUGAR 9 N28½W 23
- 1913 FARGO ENGINEERING SURVEY FOUND PTS. OF TWO OLD STAKES AT INTERSECTION OF ROADS E, W, & S. NOTED AS ESTABLISHED OR ACCEPTED IN LEGEND.
- 1972 L. GERSCHBACHER PS#18990 L.C.R.C. L.1 P.308 FOUND 1" IRON PIPE FENCE POST N30°W 31.77' 8" POPLAR S45°W 66.40' TELE. POLE S15°E 53.60'
- 1980 J.L. WILCOX & ASSOC. SURVEY J.L. WILCOX PS#14102 L.1. P.853 1" IRON PIPE N30°W 31.77' FE POST S45°W 66.44' 8" POPLAR S15°E 53.60' T.P.
- 1987 J.L. WILCOX SURVEY L.66 P.523 1" IRON PIPE. WITNESSES SAME AS L.1 P.308 1972

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-13 FOUND FARGO 1" PIPE 2.5' DOWN FLUSH WITH OLD ROAD SURFACE AND BOTTOM 2/3 OF A WEXFORD COUNTY MONUMENT 0.3' NE OF PIPE IN CENTERLINE E-W-S ROADS. ALSO FOUND REMAINS OF 1972 FENCE POST WITNESS AND IT FITS POSITION OF PIPE. REMOVED WEXFORD COUNTY MONUMENT REMAINS AND SET 5/8" X 36" IRON WITH BRASS CAP INSIDE TOP OF FARGO PIPE. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER, BEING THE SECTION CORNER COMMON TO SECTIONS 32 AND 33, T24N, R11W AND SECTIONS 4 AND 5, T23N, R11W.

Peer Group Reviewed and Approved

Date: 12-2-94

*Richard D. Wilcox*  
 Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-13 SE CORNER, SECTION 32, T24N, R11W
- 5/8" X 36" IRON WITH BRASS CAP STAMPED: CJP, 39095, 1994, 32, 33, 4, 5, SC
- N48°E 10" WHITE PINE 50.09'
- N70°W 6" POPLAR 76.20'
- S24°W 6" CEDAR 85.33'
- S28°E CORNER FENCE POST 63.51'



LIBER 04 PAGE 305

Signed by *Craig J. Pullen* 39095

NOVEMBER 30, 1994

Surveyor's Michigan License No. \_\_\_\_\_