

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1994 DEC -9 PM 2:58

For corners in
WEXFORD

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>24N</u> R <u>11W</u>	G-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

CRAIG J. PULLEN

AUGUST 17

94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-13 1838 GLO SURVEY BY J. BRINK WOOD POST HEMLOCK 12 N50½E 21 HEMLOCK 11 N87W 29
- 1913 FARGO ENGINEERING SURVEY FOUND OLD STAKE SURROUNDED BY BROKEN CROCKERY. ACCEPTED CEDAR POST COR. FENCE 8" N43E 0.56 ¾ CH CEDAR POST COR. FENCE 9" N51W 0.64 CH
- 1968 ROAD COMMISSION WITNESS BOOK ¾" PIPE WITH RIBBONED SPIKE 6" BELOW SURFACE 12" R. PINE N30°E 80.80' 24" MAPLE N75°E 80.80' P.P. SW 63.60'
- 1973 L. GERSCHBACHER PS#18990 L.C.R.C. L.1 P.304 FOUND ½" IRON PIPE 24" MAPLE N60°E 80.67' 12" PINE N20°E 80.90' P. POLE S45°W 63.70'
- 1973 MDNR SURVEY C. ROSER PS #12028 L.C.R.C. L.2 P.618 FD ½" IRON ROD, FARGO PIPE & BUTTER DISHES. ADDED STD. WEX. CO. MON. 11" R. PINE N25E 81.45' P. POLE S54W 63.95' 24" MAPLE N69E 81.62' CTR. E-W CO. RD. DUE N 2' CTR N-S CO. RD. DUE E 6' SET CEDAR POST W/LOC. TAG N45°E 47'
- 1975 J.L. WILCOX & ASSOC. SURVEY J.L. WILCOX PS#14102 L.1 P.418 FOUND WEX. CO. MON. WITNESSES SAME AS GERSCHBACHER 1973 WITNESSES.
- 1983 & 1989 J.L. WILCOX ASSOC. SURVEYS L.1 P.977, L.69 P.312, L.69 P.314 WEXFORD COUNTY MONUMENT. WITNESSES SAME AS ROSER 1973 WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 FOUND WEXFORD COUNTY MONUMENT IN FAIR CONDITION 6' EAST OF CENTERLINE 19 ROAD AND IN CENTERLINE OF 14 ROAD AND 2 PREVIOUS WITNESSES. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER, BEING THE SECTION CORNER COMMON TO SECTIONS 33 AND 34, T24N, R11W AND SECTIONS 3 AND 4, T23N, R11W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Peer Group Reviewed and Approved

Date: 12-2-94
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-13 SE CORNER SECTION 33, T24N, R11W
- WEXFORD COUNTY MONUMENT
- S54°W POWER POLE 63.95'
- N50°E 14" RED PINE 49.45'
- N21°E 16" RED PINE 81.45'
- N69°E 36" MAPLE 80.67'



LISER 04 PAGE 307

Signed by *Craig J. Pullen*
Surveyor's Michigan License No. 39095

NOVEMBER 30, 1994