

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1994 DEC -9 PM 2: 58

For corners in
WEXFORD

Linda Loughmiller
 WEXFORD COUNTY, MI
 REGISTER OF DEEDS

	Located In:		Corner Code -#
	24N	11W	
1. Public Land Survey	T _____ R _____	J-13	
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

CRAIG J. PULLEN

OCTOBER 10

94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- J-13 1838 GLO SURVEY BY J. BRINK WOOD POST W. PINE 16 N71E 14 Y. PINE 10 N65W 38
- 1973 MDNR SURVEY C. ROSER PS#12028 L.C.R.C. L.2 P.620 RE-ESTABLISHED CORNER EQUIDISTANT AND ON LINE BETWEEN SECTION CORNERS TO E. AND W. SET STD. WEXF. CO. MON. AT S. EDGE RD. 8" OAK N25°E 82.2' 6" R. PINE S30°E 101.80' 18" TWIN OAK S40W 83.92'
- 1975 J.L. WILCOX SURVEY PS#14102 L.1 P.425 FOUND WEXFORD CO. MON. WITNESSES SAME AS 1973 ROSER WITS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 FOUND WEXFORD COUNTY MONUMENT (1.5' DOWN) IN GOOD CONDITION AND 3 PREVIOUS WITNESSES IN S. EDGE OF 14 RD. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER, BEING THE ¼ CORNER COMMON TO SECTION 35, T24N, R11W AND SECTION 2, T23N, R11W.

Peer Group Reviewed and Approved
 Date: 12-2-94
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-13 S¼ CORNER SECTION 35, T24N, R11W WEXFORD COUNTY MONUMENT
- N26°E 14" WHITE OAK 82.50' (NEW NAIL)
- S31°E 8" RED PINE 101.80'
- S40°W 24" TWIN OAK 83.92'
- S53°E POWER POLE 42.52'



LISER 04 PAGE 310

Signed by *Craig J. Pullen* Date NOVEMBER 30, 1994
 Surveyor's Michigan License No. 39095