

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford (County)	Located In	Corner Code #
1. Public Land Survey	T 24N R 11W	D12
	T _____ R _____	_____
2. Property Controlling in Section	S 32 T 24N R 11W	15
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on March 20, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<u>D12</u> - Recorded survey - L. 66, Pg. 23 - J. L. Wilcox - 1987 Iron & cap N50°W 13.04' to 8" Poplar N30°W 32.38' to 3" Cedar S80°E 14.51' to 6" R. Pine S30°E 20.11' to 8" W. Pine	<u>15</u> - None
---	------------------



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<u>D12</u> - C 1/4, section 32 Found 1/2" x 18" capped iron rebar # 14102 per Rec. Survey. Calculated intersection of 1/4 lines is 0.06' W and 0.64' E. N-S Barb wire is 9± E. Barb wire in trees E-W is 42.5' S. 1/2" capped iron rebar accepted as the best available evidence of the position of the corner.	<u>15</u> - W 1/16 corner common to section 32, T24N, R11W & Sec. 5, T23N, R11W – Set 2" Alum. Cap on 5/8" x 34" Rebar per standard BLM procedure. CL. of E-W Gravel Rd. is 5' N.
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>D12</u> - Replaced 1/2" capped iron rebar with 2" stamped aluminum cap on a 5/8" X 34" rebar. N80°E 14.53' to set nail & tag in N side of 9" R. Pine (JLW) S21°E 20.04' to set nail & tag in E side of 14" W. Pine (JLW) N30°W 32.34' to set nail & tag in W side of 5" Cedar (JLW) S52°W 31.12' to set nail & tag in SE side of 16" W. Pine Set blue carsonite post with location tag 1' NE Reset steel fence post 1' W.	<u>15</u> - 2" stamped aluminum cap on a 5/8" X 34" rebar S22°W 26.40' to set nail & tag in E side of 10" Cedar S35°E 29.04' to set nail & tag in NE side of 8" Cedar S58°E 50.70' to set nail & tag in N side of 12" Cedar North 33' to set 5/8" X 34" rebar with 2" AC on line with blue carsonite post with location tag.
--	--

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/10/2003