

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford (County)	Located In	Corner Code #	
1. Public Land Survey	T <u>24N</u> R <u>11W</u>	<u>F12</u>	
	T _____ R _____	_____	
2. Property Controlling in Section	S <u>33</u> T <u>24N</u> R <u>11W</u>	<u>9</u>	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on June 6, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

F12 - None



9 - Recorded survey - L.69, Pg.314 - Daniel Scripsema -1989 Set iron.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F12 - C 1/4 Cor. section 33 - Set 2" Alum. Cap on 5/8" x 34" Rebar at intersection of 1/4 lines per standard BLM procedure. E-W Fence remains is 9' N.

9 - CE 1/16 Cor. Sec. 33 - Set 2" Alum. Cap on 5/8" x 34" Rebar per standard BLM procedure. Corner of old fences S & W is 10'± E and 6'± S.

- Reference Pt - Fd. 1/2" CIR #14102 - S87°E 1.99' from '9'. This position based on calculated position for 'F11' that didn't fit monumented position for 'F11'. 1/2" CIR #14102 not utilized as '9' in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F12 - C 1/4 section 33
2" aluminum cap stamped on a 5/8" X 34" rebar
N15°E 34.34' to set nail & tag in W side of 37" W. Pine
S70°E 20.76' to set nail & tag in SW side of 7" R. Maple
S20°W 24.46' to set nail & tag in NW side of 7" R. Maple
S62°W 46.94' to set nail & tag in S side of 17" Hemlock
Set blue carsonite post with location tag 1.4' North

9 - 2" aluminum cap stamped on a 5/8" X 34" rebar.
N32°E 29.62' to set nail & tag in SE side of 16" R. Pine
N14°W 21.99' to set nail & tag in E side of 15" R. Pine
S60°E 11.62' to set nail & tag in SW side of 3" R. Maple
S87°E 1.99' to CIR # JLW 14102 - Ref. Pt.
Set blue carsonite post with location tag 1' NW

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 11/10/2003