

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Wexford</u> (County)	Located In _____	Corner Code # _____
1. Public Land Survey	T <u>24N</u> R <u>11W</u>	<u>G10</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on March 25, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			28			28	●		27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

G10 - GLO - W. Pine 14" 1/4 Sec. Cor. - J. Brink - 1839
 - Fargo Eng. - 1913 - No US Evidence
 Set iron post and crockery
 W. Pine stub. 20" S42½°E 45 L.
 Y. Pine stub. 16" N29°E 47½ L.

- LCRC-L. 4, p. 60 and Rec. Sur. - L. 69,
 p. 429 - J. A. Ray - 1990 - Fd. 1" pipe and crockery
 (Fargo Cor.) - Set Wexford Co. Monument;
 S57°W 10" W. Pine 11.65'; N70°W 12" W. Pine 13.53';
 S59°E 8" W. Pine 56.29'; S40°E 20" WPS 29.6' (Fargo);
 N29°E 16" WPS 29.7' (Fargo)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G10 - ¼ Corner Common to Sec. 27 & 28 - Found 4" Wexford Co. Alum. Cap Monument per Ray. Both remains of Fargo's Pine BT's in place. Fargo established position by single proportion. Wexford Co. Monument accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G10 - 4" Wexford Co. Alum. Cap Monument - Add stamping "¼ S28/S27"

Set Blue Carsonite Post 1' N
 S45°W 11.58' to set N & T in NW side 14" W. Pine (JAR)
 N74°W 13.45' to set N & T in N side 16" W. Pine (JAR)
 S58°E 56.25' to set N & T in SW side 12" W. Pine (JAR)
 N58°E 30.76' to set N & T in SE side 6" W. Pine



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/10/2003