

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford Located In _____ Corner Code # _____
(County)

- | | | | | | |
|--------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>24N</u> | R | <u>11W</u> | <u>G12</u> |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on June 4, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33	●		34			35
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|--|
| <p><u>G12</u> - GLO - Hemlock 14" - 1/4 Cor. - J. Brink - 1838
 - Fargo Eng. - 1913 - No US Evidence
 Set Iron post and crockery - Lynn 14"
 S64 1/2°W 111 1/2 L.; Sugar 13" N15 3/4°W 141 1/2 L.
 - LCRC - L. 1, p. 302 and Rec. Sur. - L. 1, p.1-2 -
 L. M. Gershbacher - 1/2" iron pipe fd. - 1972
 30" Maple S80°E 38.45'; 40" Tw. Maple
 N30°W 59.70'; 28" Maple S45°W 72.44'</p> | <p>-LCRC - L. 2, p. 618 - C. F. Roser - 1973 - Fd. Fargo
 1" pipe and butter dish and old stake in CL. N-S Gravel Road. Add
 Std. Wexford Co. Mon.
 21" Maple S73°E 39.30'; 31" Maple S50°W 73.61';
 39" Maple N31°W 61.70'; set Cedar post w/ Loc. Tag E. 33';
 Fence W. is 16.5' S.
 - Rec. Sur. - L. 69, p. 314 - D. E. Schripsema - 1989
 Wexford Co. Mon. Same wit. as Roser.</p> |
|--|--|

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G12 - 1/4 Cor. Common to Sec. 33 & 34, T24N, R11W - Fd. Oxidized Wexford Co. Alum. Mon. in very poor condition. Excavated and found inverted 3/4" x 2.5" long Fargo pipe on N. side and rotten wood stake on S. side Mon. Several pieces of broken white butter dishes around Mon. in CL. of N-S Gravel Road. Fence E. is 1.5' ± S. Fd. Dead 46" S. Maple N15°E 94' to CL. - Fargo BT. Fargo established position by single proportion to GLO. Accepted Wex. Co. Mon. as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G12 - Replaced Wexford Co. Alum. Mon. w/ 4" DOC (DNR) Brass Cap on 1" x 36" Galv. Iron pipe w/ Tin Can w/ Conc. around cap -down 0.6'. Placed crockery and wood stake at base Mon. as memorials. N30°W 61.92' to Fd. Nail in NE side 45" S. Maple (LMG, CFR) S70°E 39.20' to set N & T in S. side 33" S. Maple (LMG, CFR) S49°W 73.89' to Set N & T in NW side 36" S. Maple (LMG, CFR) N65°W 81.91' to Set N & T in S. side 30" S. Maple East 33.03' to Fd. 1/2" Rebar and Reset DNR Cedar post w/ Loc. tag along side.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/10/2003