

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 28 T 24N R 11W	10
	S 28 T 24N R 11W	12
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May, 13, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

10 - None 12 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

10 - S 1/16 corner common to sections 29 & 28 - Set 2" Alum. Cap on 5/8" x 34" iron rebar Per standard BLM procedure.

12 - CS 1/16 corner section 28 - Set 2" Alum. Cap on 5/8" x 34" iron rebar per Standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p><u>10</u> - 2" stamped aluminum cap on a 5/8" X 34" rebar. S47°W 43.79' to set nail & tag in E side 6" R. Maple <i>scribed 'XBT'</i> N35°W 57.17' to set nail & tag in S side tw. 7" R. Maple <i>scribed 'XBT'</i> N18°E 55.60' to set nail & tag in E side 10" B. Fir <i>scribed 'XBT'</i> S61°E 38.83' to set nail & tag in N side of 12" Cedar Set Blue Carsonite Post with location tag 1' SW</p>	<p><u>12</u> 2" stamped aluminum cap on the 5/8" X 34" rebar S24°W 17.18' to set nail & tag in W side of 5" W. Pine S80°W 18.23' to set nail & tag in N side 4" Oak N18°E 32.40' to set nail & tag in N side 6" Ash S68°E 29.07' to set nail & tag in N side 6" W. Pine Set blue carsonite post with location tag 1' SE</p>
--	--

Signed by: Craig W. McVean Date: 11/10/2003

Surveyor's Michigan License No.: 39088