

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford			
(County)	Located In	Corner Code #	
1. Public Land Survey	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S <u>30</u> T <u>24N</u> R <u>11W</u>	<u>1</u>	
	S <u>30</u> T <u>24N</u> R <u>11W</u>	<u>2</u>	
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 22, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9	●	●											
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1 - None 2 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

1 - W 1/16 corner common to section 19 & 30 -
Set 2" Alum. Cap on 5/8" x 34" iron rebar per
Standard BLM procedure.
8' S. of E-W 2-track road.

2 - E 1/16 corner common to sections 19 & 30 -
Set 2" Alum. Cap on 5/8" x 34" iron rebar per
standard BLM procedure.
CL. of old overgrown E-W 2-track is 8' South.
In line w/ 2-track S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1 - 2" stamped aluminum cap on a 5/8" X 34"
S40°W 5.93' to set nail & tag in SE side 10" S. Maple
S70°E 13.72' to set nail & tag in N side 14" S. Maple
N30°W 29.21' to set nail & tag in SW side of twin 16" Beech
N56°E 39.74' to set nail & tag in SE side of twin 12" Beech
Set Blue carsonite post with location tag 1' NE

2 - Set 2" stamped aluminum cap on the 5/8" X 34" rebar
S73°W 66.09' to set nail & tag in S side twin 6" Spruce
S42°W 36.23' to set nail & tag in SE side 10" R. Pine
S3°E 70.80' to set nail & tag in E side 12" R. Pine
S88°E 46.04' to set nail & tag in N side 5" Cherry
Set blue carsonite post with location tag 1' NW

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 11/10/2003