

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 Wexford _____
 (County)

1. Public Land Survey	T	24N	R	11W	C10
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Section	S		T		
	S		T		
			R		

4. Lot No: _____ Recorded Plat: _____
 5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 6, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
C10 - GLO - Set 1/4 post, by J. Brink, 1839
Beech 13" S61 1/2°W 36 L.
Beech 11" N11°E 20 L.
 - Fargo Eng. - 1913 - No US evidence found.
 Set iron pipe and crockery - SP.
 Sugar Stub 14" N68 1/2°E 1.06 CH.
 -Unrecorded survey - Mitchell and Associates - Job #20010616-
 P. A. Trinklein - 2001 - found 3/4" pipe, east Centerline N-S trail
 78'; East N-S fence 51'±
 S14°E 7" White Pine 9.90'
 S55°W 10" White Pine 4.97'
 N16°W 9" White Pine 4.98'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


C-10 - 1/4 Corner Common to Sec. 29 & 30 - Found 3/4" I.D. x 2.5' long iron pipe with hooked end per Fargo Eng. and Trinklein.
Removed Fargo pipe and find 2 butter dishes. Centerline of N-S gravel road is 78' E. Fargo pipe established by single proportion and is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10 - Replaced Fargo pipe with 4" DNR aluminum cap on 1" x 36" galvanized iron pipe.
Placed butter dishes and beer bottle at base of monument as memorials. Add ring of cobbles. Set Blue Carsonite Post 1' NE
S10°E 9.88' to find. Nail in SW side 5" White Pine (PAT)
S52°W 4.93' to find. Nail in S side 7" White Pine (PAT)
N48°W 4.97' to find. Nail in SW side 6" White Pine (PAT)
N19°E 31.23' to set N & T in W side 10" White Pine scribed 'XBT'
N64°E 66.91' to set N & T in N side 20" Sugar Maple scribed 'XBT'

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/10/2003



Register of Deeds Stamp & File Number