

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 Wexford _____
 (County)

1. Public Land Survey T 24N R 11W F10
2. Property Controlling in Section S 29 T 24N R 11W 7
3. Miscellaneous S T R
S T R

4. Lot No: _____ Recorded Plat: _____
 5. Private Claims: _____

1. Craig W. McVean, in a field survey on May 13, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

- Z - Rec. Sur. - L. 69, P. 428 - J. Ray - 1990 - F10 - None
 Set 1/2" iron and cap

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Z - N 1/16 corner common to sections 29 & 28 - F10 C 1/4 corner of section 28 - Set 2" Alum. Cap
 Found 1/2" X 18" rebar per Rec. Survey. on 5/8" x 34" rebar at intersection of 1/4 line per
 1/2" rebar accepted as the best available evidence standard BLM procedure. CL. of E-W Gravel Rd. is 62' N.
 of the position of the corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Z Replaced 1/2" rebar with 2" stamped aluminum cap on a F10 - 2" stamped aluminum cap on the 5/8" X 34" rebar
 5/8" X 34" Rebar S22°E 17.25' to C/L 1" W. Pine
 S32°W 40.94' to set nail & tag in E side 22" Walnut S45°E 44.20' to set nail & tag in NE side 2" Fir
 S24°E 90.28' to set nail & tag in E side Tri. 10" Cherry N40°E 52.95' to set 1/2" X 18" rebar
 N6°W 159.17' to set nail & tag in W side 7" Cherry N47°W 73.87' to set nail & tag in SW side 9" Poplar
 N60°W 175.78' to set nail & tag in E side Tw. 6" R. Maple Set blue carsonite post with location tag 1' E
 NNE 0.3' to Face Fd. Steel Fence post Set blue carsonite post with location tag 1' E

Signed by: Craig W. McVean Date: 11/10/2003
 Surveyor's Michigan License No.: 39088