

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Wexford  
 (County)

Located In

Corner Code #

- |                                      |         |              |              |       |       |
|--------------------------------------|---------|--------------|--------------|-------|-------|
| 1. Public Land Survey                |         | T <u>24N</u> | R <u>11W</u> | D11   |       |
|                                      |         | T _____      | R _____      | _____ | _____ |
| 2. Property Controlling in Section   | S _____ | T _____      | R _____      | _____ | _____ |
|                                      | S _____ | T _____      | R _____      | _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ | T _____      | R _____      | _____ | _____ |
|                                      | S _____ | T _____      | R _____      | _____ | _____ |

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on May 13, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11			●										
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- D11 - GLO - Set 1/4 post, by J. Brink, 1839  
 Hemlock 10" S31°E 20 L.  
 Hemlock 14" N30°E 11 L.  
 - Fargo Engineering – 1913 – Found Hemlock stp. and roots of other which correspond to US notes. Found old Beech stake there but not in proper place. It was 5 L. N and 9 L. W of proper place. Set iron pipe and crockery. Cedar stp. 20" N 7 1/2°E 53 3/4 L.  
 Maple 14" S 5 1/2°E 13 1/4 L.  
 - Wilcox and Associates notes – 1977 – Found Concrete monument.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

D11 – 1/4 Corner Common to Sec. 29 & 32 – Found 4" x 36" long concrete monument with 1/2" iron in Old Field line with down fence that bears N80° W. Removed concrete monument and found inverted 3/4" x 2.5' long Fargo pipe with hooked end on E. side of monument. Dug for crockery but none found. Fargo's Wit's. fall in fields and are gone. Position fits Fargo's distances to 'C11' and 'E11' closely. Reset concrete monument in place found. Concrete monument accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D11 – 4" Concrete monument with 1/2" iron – Epoxied 2" alum. cap -properly stamped- on the 1/2" iron.  
 Set Blue Carsonite Post 1' NE  
 Set steel fence post 1' S  
 N1°W 223.49' to set N & T in W. side 16" Ash scribed 'XBT'  
 N67°E 179.44' to set N & T in N. side 18" Cedar scribed 'XBT'  
 N82°E 154.33' to set N & T in S. side 10" Cedar scribed 'XBT'  
 S44°E 193.64' to set N & T in S. side 15" Ash scribed 'XBT'  
 East 152'± to high bank of Manistee River



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 11/10/2003