

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 12 W.	A-5
2. PROPERTY CONTROLLING IN SECTION 18	T. 24 N. R. 12 W.	3; 8
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 23, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-5 Found 1/2' rerod w/cap RLS #12581. Corner is in line with center of county road grade to S & W & old twp. road grade to N. Corner fits J. H. Millard survey of Sec. 13,24-13, 1903.
- 3 Found plow point & iron per J. H. Millard survey of Sec. 13, T24N-R13W dated 1903.
- 8 Established 1/16 corner at prorated distance to G.L.O. & on line between center of Section 18 & W 1/4 corner. Corner falls in pipe line opening.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5	3	8
Set std. Wexford County Mon. & cedar post w/loc. tag	Fd. plow pt. & 3/4"x15" bolt	Set 1 1/2"x22" rod & cedar post w/loc. tag
5" Cedar N31°W 40.1	5" Walnut S44°W 40.31	5" B.Cherry N49°E 79.46
7" Hemlock N62°E 18.2	5" R. Pine N81°W 47.59	6" B.Cherry S44°E 40.17
4" Cedar S71°E 29.4	5" Walnut N64°W 28.28	24" Hemlock S13°E 91.35
	New Fn. to E Due S 5'±	10" Twn.Maple S54°W 98.30
	Set cedar post w/loc. tag Due E 33'	Old E-W Fence Due S 25'

SIGNED BY Carl F. Roser 4-28-77 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____
 WEXFORD TOWNSHIP
 WEXFORD COUNTY