

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 12 W.	B-5; B-6
2. PROPERTY CONTROLLING IN SECTION 18	T. 24 N. R. 12 W.	12
3. MISCELLANEOUS PROPERTY IN SECTION 18	T. 24 N. R. 12 W.	ZZ (1956.88 W of B-6 & 650.88 E of A-6)
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 14, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on June 23, 1976, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

** = Description of original monument and subsequent restoration.*

<p style="text-align: center;">12</p> <p>Set 1"x36" pipe-cedar post w/loc. tag</p> <p>9" R. Pine S17°E 17.0</p> <p>7" R. Pine S73°W 15.0</p> <p>8" R. Pine S23°W 22.4</p> <p>7" R. Pine N75°E 15.7</p> <p>Set 1" Pipe N89°20'E 33'</p> <p>Set 1" Pipe N00°36'E 45.27</p>	<p style="text-align: center;">C. (CONTINUED) ZZ</p> <p>Set 1½"x22" Rod-cedar post w/loc. tag</p> <p>16" B. Cherry S27°E 53.42</p> <p>5" Maple S42°E 52.44</p> <p>12" B. Cherry S58°E 62.20</p> <p>3" Pipe (gas line marker) N55°W 87.4</p> <p>Old Fence to S Due E 12'</p> <p>Old E-W Fence Due S 13.5'</p>
--	--

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- B-5 Reestablished ¼ corner on line between section corners to E & W and at prorated distance to G.L.O. survey.
 - B-6 Established center of Section 18 at intersection of ¼ lines. 1938 aerial photo shows that fence from W¼ corner E½ mile ended.
 - 12 Established 1/16 corner equidistant & on line between center of Section to N & ¼ corner to S.
 - ZZ Established NW corner of E½, frl. W½, frl. SW¼ of Section 18 as noted in item 3, code ZZ above. Corner falls in pipe line opening.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p style="text-align: center;">B-5</p> <p>Set 1½"x48" pipe & cedar post w/loc. tag</p> <p>6" Cedar S17°E 13.6</p> <p>5" Cedar S73°E 20.5</p> <p>6" Cedar N35°E 22.4</p> <p>5" Cedar N45°W 21.3</p> <p>Old poor B-W fn. on trees, Due E, 90'±</p>	<p style="text-align: center;">B-6</p> <p>Set 1½"x40" pipe & cedar post w/loc. tag</p> <p>10" R. Pine S32°E 112.9</p> <p>8" R. Pine S16°W 104.8</p> <p>8" R. Pine S42°W 99.6</p> <p>6" B. Cherry N06°W 102.8</p> <p>Set 1"x24" pipe N89°45'E 33'</p> <p>Ctr. E-W Nat. Gas Line Due S 12'±</p> <p>Old N-S Fn. Due E 18'±</p> <p>Old E-W Fn. Due S 48'±</p>
--	---

SIGNED BY Carl F. Roser 4-28-77 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

WEXFORD TOWNSHIP
WEXFORD COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____