

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 12 W.	B-7
2. PROPERTY CONTROLLING IN SECTION 18	T. 24 N. R. 12 W.	16
3. MISCELLANEOUS PROPERTY IN SECTION 18	T. 24 N. R. 12 W.	XX (627.00 W of B-7 & 2,006.82 E of A-7)
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
 FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 22, 1976, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on June 22, 1976, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B-7 B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 Found 3/4"x8" bolt, wo. stk. & various other farm iron & one Co. Surveyor Walter Johnson witness from 1916. Corner is in center of E-W gravel road & in line w/old fences N & S.

16 Established 1/16 corner per standard B.L.M. instructions.

XX Established corner as noted in item 3 code XX above (SW corner of exception to State-owned acreage). Corner is 4' N of E-W gravel road & in line w/old fence to N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7	16	XX	
Set std. Wexford Co. Monument	Drove 1 1/2"x18" rod in E-W gravel road	Drove 1 1/2"x18" rod	
6" R. Pine N26°W 55.33	32" Cherry N76°W 82.14	6" R. Pine N33°W 59.78	
6" J. Pine N58°E 110.73	8" R. Pine N43°W 83.68	15" Apple N48°E 63.37	
Set cedar post w/loc. tag	38" Dead Elm S15°E 23.27	5" R. Pine N72°E 86.92	
Due N 33'	Set cedar post w/loc. tag	Set cedar post w/loc. tag	
	Due N 33'	Due N 33'	

SIGNED BY Carl F. Roser 4-28-77 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

WEXFORD TOWNSHIP  
WEXFORD COUNTY