

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>17</u> , T. <u>24</u> , R. <u>12</u> ●	N. S., R. _____ E. W.	<u>3; 15; 16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. S., R. _____ E. W.	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 23, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 3 Found 1 1/4" pipe capped with concrete at position from McClung (Frank) survey. Corner was then destroyed by pipe line construction, but was able to reset 1" pipe from our traverse. Corner fits halfway and on line between section corner to N & 1/4 corner to S.
- 15 Established 1/16 corner per standard B.L.M. instructions.
- 16 Established 1/16 corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3	15	16
Set 1"x30" pipe-cedar post w/loc. tag	Drove 1 1/4"x18" rod in E-W gravel road	Drove 1 1/4"x22" rod in E-W gravel road
12" B. Cherry N76°E 39.8	4" S. Pine N33°E 51.51	8" Maple S47°E 44.1
6" W. Pine S58°E 59.9	5" R. Pine S38°E 82.60	4" Ironwood S42°W 28.8
8" W. Pine N72°W 75.1	5" R. Pine S15°W 61.50	7" Maple N29°W 34.2
Center N-S dirt rd.	12" Elm S08°W 18.47	5" Ironwood N38°E 52.4
Due E 15'±	Set cedar post w/loc. tag	Set cedar post w/loc. tag
Fn. cor. w/newer fn. W&S	Due N 33'	Due N 33'
Due W 46'		

SIGNED BY Carl F. Roser 4-28-77 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

WEXFORD TOWNSHIP
WEXFORD COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____