

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>24</u> N. <u>●</u> , R. <u>12</u> W. <u>●</u>	D-6; D-7
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. <u>●</u> , R. _____ W. <u>●</u>	_____
3. MISCELLANEOUS PROPERTY IN SECTION <u>20</u>	T. <u>24</u> N. <u>●</u> , R. <u>12</u> W. <u>●</u>	XXX (333.61' E of Sec. 20 code 1 & 1000.84' W of D-7)
4. LOT NO. _____	, RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 24, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on June 28, 1976, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-6 Established center of Sec. 17 at intersection of ¼ lines. There is an evident & presently used old road grade with some R-O-W fences near the E-W ¼ line, but it is highly irregular.
- D-7 Recovered old bent 3/4" pipe that fits Walter Johnson, County Surveyor, survey of N line of Sec. 20 in 1916. Corner is 2'± south of center of E-W gravel road & is in line with old fence to south.
- XXX Established NE corner of W¼ of NE¼ of NW¼ of Sec. 20, on N line of Sec. 20 N89°32'10"E, 333.61' from W 1/16 on N line Section 20.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-6	D-7	XXX
Drove 1"x24" pipe & cedar post w/loc. tag	Set std. Wexford Co. Monument	Drove 1¼"x22" rod (buried in rd.)
9" W. Pine N33°W 30.0	8" Maple clstr. N32°W 57.41	26" B. Cherry N62°W 99.83
12" W. Pine N12°W 25.2	14" B. Cherry N65°E 34.84	12" B. Cherry N12°E 65.93
10" B. Cherry N61°E 17.7	5" Maple clstr. S27°E 33.17	Set cedar post w/loc. tag
E-W narrow rd. grade Due N 39'	Set cedar post w/loc. tag	Due S 33'
4" pipe capped with concrete N06°W 32.97	Due N 33'	

SIGNED BY Carl F. Roser 4-28-77 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ WEXFORD TOWNSHIP
WEXFORD COUNTY

