

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 24 N. R. 12 W.	D-3; E-3
2. PROPERTY CONTROLLING IN SECTION 8	T. 24 N. R. 12 W.	1; 3
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 15, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~As a description of original monumentation and/or subsequent restoration~~

C. (CONTINUED)

3
Set 1"x36" pipe & ced. post w/loc. tag
12" Tri-Maple S24°E 34.9
10" Twn. B. Cherry S58°W 17.0
12" Twin Maple N30°W 13.4
6" Maple N51°E 40.3

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-3 Restored 1/4 corner in E-W dirt road 1 1/2 rods N of old corner fence post (fence S & E) with vague fence remains N for 600' & definite posts N of this point. Corner restored by this method fits survey of Section 5 by C.P. Tuller dated 1899.
- E-3 Found 5/8"x30" rod & bottom of old wood stake in position, in line with fences to N & S with E-W, R-O-W fences.
- 1 Established 1/16 corner per standard B.L.M. instructions.
- 3 Established 1/16 corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-3	E-3	1
Set 1 1/4"x22" rod	Set Wexford Co. Mon. & cedar post w/loc. tag	Drove 1 1/4"x20" rod
16" B. Cherry N75°E 97.0	10" Maple N53°E 90.1	8" Maple S89°W 102.3
18" Maple N03°E 164.1	18" Maple N09°E 72.8	16" B. Cherry S55°W 105.7
6" Twn. B. Cherry N56°W 132.4	6" Maple N03°W 79.4	4" Pipe Gate Post N58°W 43.4
Cedar post w/loc. tag Due S 33'	Old Fn. Cor. Post S02°W 25.8	4" Pipe Gate Post N34°W 50.7
	Ctr. Dirt Rd. (NW-SE) Due N 41'	Set cedar post w/loc. tag Due S 33'

SIGNED BY Carl F. Roser 4-28-77 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ WEXFORD TOWNSHIP
WEXFORD COUNTY