

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 24 N. R. 12 W.	B-3; C-3
2. PROPERTY CONTROLLING IN SECTION 6 _____	T. 24 N. R. 12 W.	14; 16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 21, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and subsequent restoration~~

C. (CONTINUED) 16  
 Set 1 1/2"x72" pipe & cedar post w/loc. tag  
 9" Cedar S04°E 20.5  
 12" Maple N82°E 33.9  
 10" Cedar N40°E 53.1  
 7" Cedar N40°W 28.4

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-3 Recovered cedar stake bottom in swp. from three Walter Johnson witnesses, 1916.
- C-3 Recovered pt'd. cedar stake bottom from hemlock stp. & stub w/partial lower face, S45 1/2°E 40', per Walter Johnson survey, 1916. Notes in large red Co. Surveyor's Liber at Co. Rd. Comm., pages 212 & 213. Johnson fd. govt. stk. & one U.S.B.T. as recovered by C.P.Tuller in survey of Sec. 5, Jan. 1899, Tuller's notes located in field book #83 pages 144-150, his notes in possession of T.C.Tuller, Rapid City, Michigan.
- 14 Recovered ptd. ced. corner post bottom in muck from one C.P.Tuller 1899 wit. Elm 6" N01°W 19'; w/old N-S w-w fence in muck, Fits U.S. stream tie of 1 chain South.
- 16 Restored 1/16 cor. from Johnson wit. (cedar stp.) his survey of S-6 1916. Corner falls in old, overgrown E-W woods swamp trail.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3	C-3	14
Set std. Wexford Co. mon. on 1 1/2" pipe & cedar post	Fd. stk. bottom & replaced w/ State of Mich. Mon. & ced. post	Drove 1 1/2"x60" pipe-cedar post w/loc. tag
9" Cedar S22°W 18.3	9" Maple S85°W 8.6	8" Cedar S03°W 61.4
12" Hemlock S15°E 31.0	7" Maple S15°W 17.0	9" Cedar S40°W 44.7
10" Cedar N77°E 20.3	7" Maple S84°E 27.0	11" Cedar S72°W 52.2
10" Cedar N22°W 33.5	18" Hemlock N52°E 39.0	12" Cedar N78°W 58.1
	Ctr. pipe line opening Due W 50'±2'	
	Old Cor. Fn.Post (now destroyed by pipe line const.) N19°37'W 37.7	

SIGNED BY Carl F. Roser DATE 4-28-77

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR



WEXFORD TOWNSHIP  
WEXFORD COUNTY