

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 24 N. R. 12 W. ●	A-2
2. PROPERTY CONTROLLING IN SECTION 6 _____	T. 24 N. R. 12 W. ●	8; 9
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 22, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A = Description of monument and accessories established or subsequent restoration:~~

B. (CONTINUED)

pointed stake by down fence corner (fence N & E) and adjusted well point to a position of 5.0' South to fit Johnson survey prorated.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-2 Fd. 1" pipe 6' W of N-S dirt road. Fits previous survey by Walter Johnson, dated 1916.
- 8 Recovered well pt. per Johnson survey of Sec. 6 in 1916. Old fence remains to N & W. Johnson's survey record, in large red Liber, pages 212 & 213 at Wexford Co. Rd. Comm. indicate he split the frl. NW $\frac{1}{4}$ of Sec. 6 exactly in half E & W. Tax desc. for dates 1911, 1914 1916 & 1917 show W $\frac{1}{2}$ of frl. NW $\frac{1}{4}$ S-6 as 90 Ac. (G.L.O. = 89.15 Ac) & E $\frac{1}{2}$ of frl. NW $\frac{1}{4}$ S-6 as 90 Ac. (G.L.O. = 90.45 Ac) State deed No. 72320, Nov. 29, 1939, reads E $\frac{1}{2}$ of NW frl. $\frac{1}{4}$ S-6. Warranty Deed, Liber 115, page 215, 1922± reads W $\frac{1}{2}$ of NW frl. $\frac{1}{4}$ S-6. Accepted split of NW frl. $\frac{1}{4}$ per Walter Johnson survey.
- 9 Restored 1/8 corner prorated to Walter Johnson survey dated 1916. Fd. well pt. & (see above)
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2	8	9
Fd. 1"x20" pipe-add 1 $\frac{1}{4}$ "x20" iron rod & ced.post w/loc. tag	Fd. well pt. & set cedar post w/loc. tag	Reset well pt. & set cedar post w/loc. tag
12" B. Cherry S70°E 25.2	5" Pin Cherry N07°W 26.8	14" Hemlock Due N 30.4
8" Apple S18°W 19.8	10" B.Cherry in cluster of 3 S39°E 60.3	17" Cedar N85°E 17.6
9" Maple N64°W 51.5	18" B.Cherry S05°W 54.0	14" Maple S35°E 13.8
11" B. Cherry N27°W 50.2	20" B.Cherry S86°W 92.1	E-W Random Due S 3'
	1/16 Cor. (S.P. to U.S.) is S89°36'W, 3.88'; set 1"x42" Re-rod w/DNR Cap & Ced. Post	

SIGNED BY Carl F. Roser DATE _____
4-28-77

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

WEXFORD TOWNSHIP
WEXFORD COUNTY