

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 NOV 30 AM 10:45

RECEIVED

Linda Doughmiller
WEXFORD COUNTY, MI
REGISTERED DEEDS

For corners in
WEXFORD

(County)

Located In:

Corner Code #

1. Public Land Survey		T	24N	R	12W		M-12
		T		R			
		T		R			
		T		R			
2. Property Controlling in Section	S	T		R			
	S	T		R			
3. Miscellaneous Property in Sec.	S	T		R			
	S	T		R			

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, **CRAIG J. PULLEN** in a field survey on **JUNE 1**, 19**94**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-12 1836 GLO SURVEY BY J. BRINK WOOD POST SUGAR 14 S62W 20 SUGAR 11 N67W 07
- 1915 FARGO ENG. SURVEY NO U.S. EVIDENCE TELEGRAPH POLE 11" S39 1/4 1.47 1/2 TELEGRAPH POLE 12" N48W 1.39 1/2
- 1971 P. PERLA #5942 SURVEY L.246 P.577 1/2" IRON NE 141.81' 16" APPLE SE 71.14' 24" ELM
- 1976 WILCOX & ASSOC. #14102 SURVEY L.1 P.397 & L.C.R.C. L.2 P.795 WEX. CO. MONS. 55°E TEL. RISER 33.36' S75°W FENCE POST 90.76' WEST CENTERLINE M-37 33.00'
- 1978 WILCOX & ASSOC. #14102 SURVEY L.1 P.613 WEX CO MON. WEST CENTERLINE M-37 31.67' S78°W FENCE POST 90.80' N25°W FENCE POST 144.62'
- 1979 MSHD SURVEY M-37 FOUND BRASS DISC IN MON. BOX 33'E. OF CENTERLINE M-37 S20°E 11.67' WOOD SIGN POST S40°E 14.98 WOOD SIGN POST S5°E 33.15 FACE OF U.G. TEL. CABLE PEDESTAL
- 1985 WILCOX & ASSOC. #14102 SURVEY L.2 P.144 WEX. CO. MON. WITS. SAME AS L.2 P.795 L.C.R.C.
- 1987 WILCOX & ASSOC. P. CASE #30079 WEX. CO. MON. CALLS L.1 P.397
- 1988 WILCOX & ASSOC. D. SCHRIPEMA #24617 L.66 P.513 WEX. CO. MON. S34°E 6.28' SIGN POST S16°E 11.71' SIGN POST N47°E 29.27 2" WILD CHERRY N18°E 63.04' 4" WILD CHERRY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-12 FOUND WEXFORD COUNTY MONUMENT IN MON. BOX AND 2 WITNESSES FROM L.66 P.513. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Peer Group Reviewed and Approved

Date: 11-21-94
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-12 E 1/4 CORNER, SECTION 36, T24N, R12W AND THE W 1/4 SEC. 31 T24N R11W
WEXFORD COUNTY MONUMENT
- S23°E WEST POST OF CANOE SIGN 11.05'
- N45°E 2" ELM IN FENCE LINE 72.05'
- WEST CENTERLINE M-37 31.67'
- N76°W 6" RED PINE 115.15'

CONSTRUCTION POINT

Signed by *Craig J. Pullen* Date SEPTEMBER 22, 1994
Surveyor's Michigan License No. 39095

