

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S 31 T 24N R 12W CWE 1/64  
S 21 T 24N R 12W 8

3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on June 3, 2008 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

CWE 1/64 of Section 31 - 2005 - Unrecorded survey - 8 - None.  
Nordlund & Assoc. - File # PS05-287 - R. M. Slawinski -  
Set corner

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

CWE 1/64 Corner of Section 31 - being the NE corner of the W 1/2 of the W 1/2 of the SE 1/4, Sec. 31 - Found 1/2" x 24" capped iron rod # 16345 per Nordlund Survey. Falls in old E-W Field Furrow. Line of Steel Fence posts run S & E from corner. 1/2" CIR accepted as best available evidence of the position of the corner.

8 - CW 1/16 Corner Section 21 - Set stamped 2" Aluminum cap on 5/8" x 34" rebar per Standard BLM procedure. Corner of barb wire fence remains on ground and in trees E, W & N is 33'± E & 10'± S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

CWE 1/64 of Section 31 - Replaced found 1/2" x 24" capped iron rod #16345 with a stamped 2" Aluminum Cap on 5/8" x 34" rebar. S45°W 30.01' to set nail & tag on SE side 30" Sugar Maple S26°E 30.40' to set nail & tag in W. side 7" R. Pine N83°W 36.40' to set nail & tag in N. side 4" Jack Pine Set Blue Carsonite Post with location tag 1' NW N21°E 6.00' to set nail & tag in E. side 3" Beech

8 -- Stamped 2" Aluminum cap on 5/8" x 34" rebar S48°W 15.88' to set nail & tag on W. side 9" Sugar Maple N47°W 40.64' to set nail & tag on S. side 12" & 16" Twin Ash S46°E 15.47' to set nail & tag on SW side 8" Sugar Maple Set Blue Carsonite Post with location tag 1' West N49°E 22.88' to set N & T in NW side 8" Sugar Maple

Signed by: \_\_\_\_\_

Craig W. McVean

Date: \_\_\_\_\_

1/14/2009

Surveyor's Michigan License No.:

39088

