

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Wexford Located In _____ Corner Code # _____
 (County)

1. Public Land Survey T _____ R _____
 T _____ R _____

2. Property Controlling in Section S 31 T 24N R 12W WE 1/64
 S _____ T _____ R _____

3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on June 2, 2008 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

WE 1/64 Corner common to Sec. 31, T24N, R12W and Sec. 5, T23N, R12W - None

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

WE 1/64 Corner common to Sec. 31, T24N, R12W and Sec. 5, T23N, R12W – Being the SE Corner of the W ½ of the W ½ of the SE ¼, Sec. 31 – Set stamped 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure. Falls 1' North of Centerline of E-W Bit. Rd.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

WE 1/64 Corner common to Sec. 31, T24N, R12W and Sec. 5, T23N, R12W – 2" Aluminum Cap on 5/8" x 34" Rebar North 33.00' to set 2" Aluminum Cap on 5/8" x 34" rebar on line with Blue Carsonite Post with loc. Tag S54°W 79.14' to set N & T in NW side 6" R. Pine S22°E 50.01' to set N & T in W. side 11" R. Pine N62°W 66.67' to set N & T in SW side Power Pole



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 1/14/2009