

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ 12 T. _____ 1 S., R. _____ 3 E.		M-3, M-4
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Washtenaw Co

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March, 1987, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>M-3 NE Corner Section 12                  Found 1" Pipe in Concrete Mon.                  N10°W-2.1'-16" Oak                  N45°E-12.1'-14" Hickory                  N25°E-15.8'-10" Oak                  N5°W-35.4'-16" Oak                  North-19.90'-<math>\frac{1}{2}</math>" Pipe</p>	<p>M-4 E<math>\frac{1}{4}</math> Corner Section 12                  Set 4" x 36" Concrete Mon. with aluminum cap at half distance between SE Corner Sec. 12 and NE Cor. Sec. 12 and on a projected line from the NE Cor. Sec. 12, T1S, R3E and the W<math>\frac{1}{4}</math> Cor. Sec. 7, T1S, R4E.</p>
--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>M-3 NE Corner Section 12                  N10°W-2.1'-16" Oak                  N45°E-12.1'-14" Hickory                  N25°E-15.8'-10" Oak                  N5°W-35.4'-16" Oak                  North-19.90'-<math>\frac{1}{2}</math>" Pipe</p>	<p>M-4 E<math>\frac{1}{4}</math> Corner Section 12                  4" x 36" Concrete Monument with aluminum cap.                  North-8.33'-Iron-W<math>\frac{1}{4}</math> Cor. Sec. 7(P.L.B.19826)                  N07°E-31.91'-24" Oak in old fence row.                  N60°E-53.30'-19" Oak in old fence row.                  S80°W-33.01'-18" Oak                  North-48.33'-Plat Mon.</p>
--	--


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Donald L. Bissell DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 18655