

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY: <u>2</u> T. <u>1</u> S., R. <u>3</u> E.		<u>K-1, J-1</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. S., R. _____, E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. S., R. _____, E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-1 Set 6" diameter concrete monument with aluminum cap. Placed monument on the base line and on line with an old fence going south.
- J-1 Set 4" x 36" concrete monument on the base line and in line with fence going south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| <p>K-1 6" concrete monument with aluminum cap.
S 04° W, 58.25', 3" Walnut
N 71° E, 27.15', 3" Soft Maple
N 84° W, 12.80', 12" Pin Oak
S 00-04-39 E, 500.28', Meander Corner
N 89-55-47E, 435.82', S 1/4 corner,
Section 36 (Concrete monument)
All distances are to nails and tags
in the trees.</p> | <p>J-1 4" x 36" concrete monument.
S 70° W, 35.79', 10" W. Oak
N 68° W, 10.53', 10" W. Oak
S 47° E, 4.64', 18" W. Oak
N 07° E, 6.38', Fence Corner
All distances are to nails and
and brass washers in the trees.</p> |
|--|---|

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE 11-3-80
CHEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

