

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>2</u>	T. <u>1</u> S., R. <u>3</u> E.	I-2
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

I-2 30" Oak, N 85° W, 125.6'	West from centerline Hadley Road along
12" Twin Oak, N 70° E, 41.5'	fence 364.5' to west line section, thence
Tri-Cherry, N 88° E, 56.3'	south 16.1' to W 1/4 corner.
Fence line, northerly, 16.1'	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-2 1" Pipe from above witnesses, piled rocks around pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-2 W 1/4 corner, Section 2
 1" Pipe with rocks piled around.
 S 68° E, 12.48', 6" Hickory, Spike and Tag
 N 84° W, 38.80', 24" Hickory, Spike and Tag
 North, 15.9', E-W Fence


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE 11-3-80
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 18655