

**SURVEY & REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich, P.A. 1970

NOV 02 1999

For corner in  
Washtenaw  
(County)

Located in:

Corner Code #

SECTION

- |                                    |   |           |   |           |
|------------------------------------|---|-----------|---|-----------|
| 1. Public Land Survey              | T | <u>1S</u> | R | <u>3E</u> |
|                                    | T | _____     | R | _____     |
|                                    | T | _____     | R | _____     |
|                                    | T | _____     | R | _____     |
| 2. Property Controlling in Section | S | _____     | T | _____     |
|                                    | S | _____     | T | _____     |
| 3. Miscellaneous Property in Sec   | S | _____     | T | _____     |
|                                    | S | _____     | T | _____     |



**5017322**  
 Page: 1 of 2  
 02/25/1999 02:59P  
 L-2 P-208

Peggy M. Haines - Washtenaw Co. CORREM

-copy Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Charles C. Wilson, in a field survey on June, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instruction of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- United States Government Survey, 1815 Instructions, Surveyed 1825
- Bearing Trees A) B. Oak 38" N32-1/2deg.W 30.36
- B) B. Oak 7" S60deg.E 72.60

Continued on Back

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


Found 1-1/4" Iron Pipe with stones and bricks, 6" below ground surface. Raised with 3/4" Iron Pipe and Remonumentation Cap Stamped #13604.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 3/4" Iron Pipe with Remonumentation Cap Stamped #13604 over 1-1/4" Iron Pipe.
- 1) 36" Oak N10deg.E 2.21 (Nail & RT E/S)
- 5) Stump S10deg.W 39.5+-
- 8) 12" Cherry W'y 12.15 (Nail & RT S/S)
- 12" Elm N40deg.E 12.04 (Nail & RT SE/S)
- 8" Birch N85deg.E 12.02 (Nail & RT S/S)
- 8" Cherry S40deg.W 9.0 (Nail & RT SE/S)

I feel that this point should be accepted as the best available evidence of the position of the original corner.

This corner was ratified by the Peer Committee on August 10, 1998.



Signed by Charles C. Wilson  
 Surveyors Michigan's License No. 13604

Date August 10, 1998

**APPROVED**  
 DATE 8-10-98  
 CO. REP. Ka

COPY

K-7

Paragraph A continued:



5017322  
Page: 2 of 2  
02/25/1999 02:59P  
L-2 P-209

Washtenaw County Road Commission, WCRC Book 134, Page 30, 1934  
Oak Stake 2.0 South, 0.4 East of Fence Corner

- Copy -

Washtenaw County Road Commission, W.J. Armstrong PLS#2444, October 1941  
WCRC Grid Book,  
Found Old Wood Stake.

Reset with 1-1/4"x42" Iron Pipe, Stones & Bricks.

- 1) 20" B. Oak N10deg.W 2.5
- 2) 10" B. Oak S15deg.W 16.07
- 3) 6" B. Oak S20deg.W 14.9
- 4) 10" B. Oak S22deg.W 16.2

Consumer Power Company, E.J. McCombs, PLS#10696, November 1965  
Witness Sheet, Found 1-3/4" Iron Pipe

- 1) 24" Oak N5deg.E 2.3
- 2) 20" Oak S22deg/W 15.85
- 5) Twin Oak S10deg.W 39.45

Washtenaw Eng. Co., Inc., Norman N. Fahrner, PLS#17620, April 1977  
Survey Drawing, Found 1-1/2" Iron Pipe

- 1) 20" B. Oak N10deg.W 2.5
- 2) 10" B. Oak S15deg.W 16.07
- 3) 6" B. Oak S20deg.W 14.9
- 4) 10" B. Oak S22deg.W 16.2

Atwell-Hicks, Inc., John L. Snyder, PLS#13352, February 1982  
Survey Drawing, Found 1-1/4" Iron Pipe

- 1) 36" Oak North 2.7
- 3) 14" Oak N20deg.E 34.3
- 7) 10" Oak S68deg.E 34.4
- 8) 6" Cherry S70deg.W 12.4
- 9) Fence S'ly West 2.3
- 10) E-W Fence North 2.0

C. Wilson & Associates, Inc., Craig A Eckfeld, PLS#33135, March 1988  
Land Corner Recordation Certificate, Liber 7, Page 155  
Found 1-1/4" Iron Pipe

- 1) 36" Oak North 2.7
- 6) 14" Oak N20deg.E 34.3
- 7) 10" Oak S68deg.E 34.4
- 8) 6" Cherry S70deg.W 12.4

SURVEY &  
REMONUMENTATION

NOV 02 1999

SECTION

