

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich, P.A. 1970**

**SURVEY &  
REMONUMENTATION**

NOV 02 1999

For corner in

Washtenaw  
(County)

Located in:

Corner Code #

SECTION

1. Public Land Survey

T 1S R 3E

M-8

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

5017329  
Page: 1 of 2  
02/25/1999 02:59P  
Peggy M. Haines - Washtenaw Co. CORREM L-2 P-222

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Charles C. Wilson, in a field survey on June, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instruction of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- United States Government Survey, 1815 Instructions, Surveyed 1824
- Bearing Trees A) B. Oak 13" N65deg.W 24.42
- B) B. Oak 13" N13deg.E 11.88

Continued on Back

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found Boat Spike 2" below bituminous road surface (Stofer Road). Removed and found 3/4" Iron Pipe and pieces of brick 30" below road surface. Raised 3/4" Iron Pipe with a 1" Iron Pipe and Remonumentation Cap Stamped #13604 to road surface.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1" Iron Pipe with Remonumentation Cap Stamped #13604 (at road surface)
- 3) 48" Oak S83deg.W 38.15 (Nail & RT S/S)
- 4) 44" Oak S25deg.W 58.30 (Nail & RT SE/S)
- 7) 1 R/W Pipe E'y 33.0
- 8) NW Corner of the S'y most Brick Pillar S25deg.E 96.00 (at ground level)
- 9) 17" Oak N30deg.E 85.80 (Nail & RT NW/S)
- 10) 22" Oak N80deg.E 36.36 (Nail & RT S/S)
- 11) 14" Cherry W'y 32.00 (Nail S/S)

I feel that this point should be accepted as the best available evidence of the position of the original corner.

This corner was ratified by the Peer Committee on August 10, 1998  
Monument Box will be installed by Washtenaw County Road Commission at a future date.

Signed by Charles C. Wilson  
Surveyors Michigan's License No. \_\_\_\_\_

Date August 10, 1998



APPROVED  
DATE 8-10-98  
CO. REP. \_\_\_\_\_

COPY

SURVEY &  
REMONUMENTATION

NOV 02 1999

M-8

SECTION

Paragraph A Continued:

Yocum, 1850+-

Atwell-Hicks Book 532, Page 44

C) Hickory N86-1/2deg.E 26.4



5017329  
Page: 2 of 2  
02/25/1999 02:59P  
L-2 P-223

Atwell-Hicks Book 532, Page 44, May 1928

Found Yocum's Witness Tree

C) 20" Hickory N86deg.E 26.4 1) 6" W. Oak N22deg.E 58.3

2) 12" B. Oak N25deg.W 43.4

3) 12" B. Oak S83deg.W 37.4

-copy-

W.J. Armstrong, PLS#2444, May 1935

Washtenaw County Road Commission Grid Book

Found Yocum's Witness Tree.

Reset corner with Iron Pipe Stones & Bricks

1) 6" W. Oak N22deg.E 58.3

3) 12" B. Oak S83deg.W 37.4

4) 12" B. Oak S25-1/2deg.W 58.2

5) 15" Hickory N22deg.E 65.3

6) 18" Hickory S20deg.E 72.8

7) 2 R/W Pipes E&W

C. Wilson & Associates, Inc., Charles C. Wilson, PLS #13604, September 1977

Survey Drawing

Found Boat Spike

1) 12" W. Oak N22deg.E 58.3 (nail)

3) 38" B. Oak S83deg.W 38.0 (nail)

4) 24" B. Oak S25-1/2deg.W 58.45 (nail)

C. Wilson & Associates, Inc., Charles C. Wilson, PLS #13604, May 1978

Survey Drawing

Found Boat Spike

1) 12" W. Oak N22deg.E 58.3 (nail)

3) 38" B. Oak S83deg.W 38.0 (nail)

4) 24" B. Oak S25-1/2deg.W 58.45 (nail)

C. Wilson & Associates, Inc., Charles C. Wilson, PLS #13604, October 1978

Land Corner Recordation Certificate. Liber 5, Page 104

Found Iron Bar

1) 12" W. Oak N22deg.E 58.3 (nail)

3) 38" B. Oak S83deg.W 38.0 (nail)

4) 24" B. Oak S25-1/2deg.W 58.45 (nail)

C. Wilson & Associates, Inc., Charles C. Wilson, PLS #13604, February 1979

Survey Drawing

Found Boat Spike

1) 12" W. Oak N22deg.E 58.3 (nail)

3) 38" B. Oak S83deg.W 38.0 (nail)

4) 24" B. Oak S25-1/2deg.W 58.45 (nail)

Washtenaw Engineering Co., Inc., Norman N. Fahrner, PLS#17620, September 1985

Survey Drawing

Found Boat Spike

1) 12" Oak N22deg.E 58.3 (nail)

3) 12" Oak S83deg.W 38.06 (nail)

4) 24" Oak S25deg.W 58.4 (nail)

8) NW corner Brick Pillar S25deg.E 96.07

Atwell-Hicks Grid Book

Found Boat Spike

4) 30" Oak S30deg.W 57.92 (nail SE/S)

9) 12" Oak N30deg.E 85.77 (nail NW/S)

10) 12" Oak N80deg.E 36.51 (nail N/S)

11) 14" Oak West 32.00 (nail S/S)