

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

Washtenaw (County)

Located In:

Corner Code #

1. Public Land Survey

T 1S R 4E

G11

Copy

2. Property Controlling in Section
3. Miscellaneous Property in Sec.

S T R
S T R
S T R
S T R



5094755
Page: 1 of 2
02/07/2000 02:55P

Peggy M. Haines - Washtenaw Co. CORREM L-3 P-31

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claim

I, R. Timothy Tietsema, in a field survey on 8 February, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A circled '1' is in row 11, column G.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with columns: Date, Name, Survey, Description, Monument, Distance. Includes entries for 1825, 07/29/1935, 07/08/1971, 04/25/1974, and 05/10/1979.

Continued on back.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" iron pipe with brick and stone using accessories 5,6,8,13,and 14.

APPROVED

DATE 11/22/99

CO. REP. [Signature]


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Reset with 3/4" Iron Pipe with Washtenaw County Remonumentation Cap with Michigan State Plane Coordinate values of North 312,020.25 and East 13,233,499.16. Accessories perpetuated or established as following:

Table with columns: Monument, Distance, Description. Lists items like 5) 18" Oak, 6) 12" Hickory, 8) 3"x3" Iron Angle Post, 13) 12" Elm, 14) 12" & 4" Twin Elm, 16) 12" Oak.

I find that this corner represents the best available evidence for the position of the original corner. This corner was ratified by the Washtenaw County Peer Committee on November 22, 1999.

Signed by [Signature] Date NOV 22 1999
Surveyor's Michigan License No. 20712




Continued from A.

07/20/1988	Craig Eckfeld #33135	LCRC L7P181	Found 1 1/2" iron pipe	5) 18" Hickory 6) 16" Hickory 8) Fence Post 13) 10" Elm 14) 10" & 4" Twin Elm	N20E S20W NW'y S78W N84W	20.32' 8.14' 1.7' 9.95' 15.23'
08/16/1988	C. Wilson & Assoc. Job. No. 88224 A CAE #33135	Survey	Found 1 1/2" iron pipe	5) 18" Hickory 6) 16" Hickory 8) Fence Post 13) 10" Elm 14) 10" & 4" Twin Elm	N20E S20W NW'y S78W N84W	20.32' 8.14' 1.7' 9.95' 15.23'
07/08/1992	C. Wilson & Assoc. Job. No. 92061 CAE #33135	Survey	Found 1 1/2" iron pipe	5) 18" Hickory 6) 16" Hickory 8) Fence Post 13) 10" Elm 14) 10" & 4" Twin Elm	N20E S20W NW'y S78W N84W	20.32' 8.14' 1.7' 9.95' 15.23'
01/29/96	C. Wilson & Assoc. Job No. 95092 CCW #13604	Survey	Found 1 1/2" iron pipe	5) 24" Oak 6) 16" Oak 13) 16" Ash 14) 16" Ash 15) 20" Walnut	N'y S10W S80W W'y S20E	20.12' 8.35' 10.00' 15.00' 23.45'

REF 93-2000
2000

- Copy -



5094755
Page: 2 of 2
02/07/2000 02:55P
Peggy M. Haines - Washtenaw Co. CORREM L-3 P-32

SECTION

