

REF

2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Corners in

Washtenaw
(County)

Located In:

Corner Code #

Public Land Survey

T 1S R 4E

H9

Copy

Property Controlling in Section
Miscellaneous
Property in Sec.

S T R
S T R
S T R
S T R



5094758

Page: 1 of 1
02/07/2000 02:55P

Peggy M. Haines - Washtenaw Co. CORREM L-3 P-35

Register of Deeds Stamp & File Number

Lot No. , Recorded Plat
Private Claim

Grid table with columns A-M and rows 2-13. Cell (9, I) contains a circled '9'.

B. Timothy Tietsema, in a field survey on 30 August, 1999, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

Table with 4 columns: Date, Name, Description, and Details. Includes entries for 1825 and 11/16/1970.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:


No evidence of previous monumentation or accessories were found in the vicinity of corner location. The corner location was re-established by single proportionate measurement. The corner is placed midway and on line between the NW corner (G-9) and the NE corner (I-9) of Section 27.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2" iron rod with Washtenaw County Remonumentation Cap with Michigan State Plane Coordinate values of North 317,393.05 and East 13,235,936.10. Accessories established as follows:

- 3) 36" Oak N85W 70.38' Set P.K. nail with remonumentation washer on South side
4) 36" Walnut East 54.82' Set P.K. nail with remonumentation washer on South side
5) Wood fence post N58W 5.46' Set P.K. nail with remonumentation washer on South side
6) Wood fence post S72E 13.81' Set P.K. nail with remonumentation washer on North side
7) East end of chain S13E 29.30' link fence
8) Found 3/4" iron pipe East 6.38' SE Property corner 6.00 Ac. Parcel to the NW, C. Wilson & Assoc.

APPROVED
DATE 11/22/99
CO. REP.



I find that this corner represents a careful and faithful reestablishment of the position of the original corner based upon the best available evidence. This corner was ratified by the Washtenaw County Peer Committee on November 22, 1999.

Signed by [Signature]
Surveyor's Michigan License No. 20712

Date NOV 22 1999