

RFI

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

for Corners in

Washtenaw (County)

Located In:

Corner Code #

Public Land Survey

T 1S R 4E

H13

Property Controlling in Section Miscellaneous Property in Sec.

S T R S T R S T R S T R



5094760 Page: 1 of 1 02/07/2000 02:55P

Register of Deeds Stamp & File Number

Lot No. Recorded Plat Private Claim

Grid table with columns A-M and rows 2-13. A small circle is marked at row 12, column H.

R. Timothy Tietsema, in a field survey on 11 March, 1999, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

Table with columns: Date, Surveyor, Survey, Found, Monument/Accessory, Bearing, Distance. Includes entries for J. Wampler (1825), S.B. Pettibone (Date Unknown), Atwell-Hicks (12/29/61), Glenn E. Richard (11/09/1972), Land Surveying Consultants (July 1985), C. Wilson & Assoc. (July 1985), and Land Surveying Consultants (Jan. 1998).

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron pinch pipe using accessories 3 and 8.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Washtenaw County Remonumentation Cap on existing 3/4" iron pinch pipe with Michigan State Plane Coordinate values of North 306,856.43 and East 13,236,349.28. Accessories as perpetuated or as established as follows:

Table with columns: Monument/Accessory, Bearing, Distance, Description. Includes items like '3) N 1/4 corner Sec. 3 T2S, R4E', '8) East face utility tower #12444', and '11) 6" & 8" Dbl. Poplar'.

APPROVED DATE 11/22/99 CO. REP. KA



I find that this corner represents the best available evidence for the position of the original corner. This corner was ratified by the Washtenaw County Peer Committee on November 22, 1999.

Set by [Signature]

Date NOV 22 1999

Surveyor's Michigan License No. 20712