

SURVEY & REMONUMENTATION

MAY - 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Washtenaw

(County)

Located In:

Corner Code #/

| | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>1S</u> R <u>4E</u> | <u>I-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

-COPY-
PEGGY M. HAINES
COUNTY CLERK/REGISTRAR

RECORDED
WASHTENAW COUNTY, MI
DEC 1 11 25 AM 1994

LIBER 1 PAGE 116 Rm

Register of Deeds Stamp & File Number

I, R. Timothy Tietsema, in a field survey on April 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| DATE | SURVEYOR | LS# | LCRC | SURVEY | MONUMENT DESC. | WITNESSES |
|------------|-----------------|-----|------|------------|---|--|
| 1819 | GLO (Wampler) | | | Fld. Notes | Set Original Corner of Sections 22, 23, 26 & 27. | 1) 34" W. Oak N10E 123 links(81.18') 2) 30" B. Oak S75W 189 links(124.74') |
| 11/17/1934 | W. J. Armstrong | | | Resurvey | Fnd old wood stake. Reset with 1 1/2" x 40" IP, bricks, and stones. | 3) 36" Elm S08E 25.8' 4) 14" Elm S30.5W 65.4' 5) 30" B. Oak S51W 66.2' 6) 8" W. Oak S51W 86.3' 7) 10" B. Ash S62W 31.6' 8) 10" Hickory S64W 72.0' 9) 10" W. Oak S71W 101.4' 10) 10" B. Ash S88W 35.9' |

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In April of 1994, LSC found a 1 1/2" iron pipe using these witnesses:

| | |
|--|------------------------------|
| Fnd 1/2" Iron Pipe (inside dia. smashed) | 7) 10" B. Ash S62W 31.6' |
| | 10) 14" Ash S88W 35.92' |
| | 12) 12" Box Elder S40E 8.42' |
| | 13) 12" Box Elder N15E 6.51' |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | | | | |
|---------------|----------------|-------|--------|---|---|
| April 20 1994 | R. T. Tietsema | 20712 | Remon. | Fnd. 1 1/2" Iron Pipe | 7) 22" Ash S60W 31.45' to nail & R.T. |
| | | | | 5.45' E. of N-S fence, | 10) 22" Ash WEST 35.51' to nail & R.T. |
| | | | | 3' E. of N-S gravel road | 12) 15" Ash S30E 8.31' to nail & R.T. |
| | | | | (inside dia. 1/2" smashed) | 13) 14" Box Elder N50E 6.30' to nail & R.T. |
| | | | | (no brick found). Added a Wash. Co. Remon. Cap. | |

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by R. Timothy Tietsema
Surveyor's Michigan License No. 20712

Date October 3 1994

CONTINUED FROM A. ON FRONT:

| DATE | SURVEYOR | LS# | LCRC | SURVEY | MONUMENT DESC. | WITNESSES |
|---------------|---------------------------------|-------|--------|----------|---|---|
| 4/21/1979 | Charles C. Wilson | 13604 | L5P257 | | Fnd. 1 1/2" Iron Pipe | 3) Large Stump S08E 25.8' 7) 14" B. Ash S62W 31.6' 10) 14" B. Ash S88W 35.9' 11) 12" B. Walnut N62W 72.4' |
| December 1987 | R. T. Tietsema JOB NO: 19287 | 20712 | | Boundary | Fnd 1/2" Iron Pipe (inside dia. smashed) | 10) 14" Ash S88W 35.92' 12) 12" Box Elder S40E 8.42' 13) 12" Box Elder N15E 6.51' 14) 5.45' East of a N-S Fence Line |
| October 1990 | R. T. Tietsema JOB NO: 15190 | 20712 | | Boundary | Fnd 1/2" Iron Pipe (inside dia. smashed) | 10) 14" Ash S88W 35.92' 12) 12" Box Elder S40E 8.42' 13) 12" Box Elder N15E 6.51' 14) 5.45' East of a N-S Fence Line |

APPROVED
 DATE 5/3/1994
 CO. REP. [Signature]